

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐
(highlight changes)

APPLICATION FOR PERMIT TO DRILL				5. MINERAL LEASE NO: ML-48176	6. SURFACE: State
1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>				7. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A	
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/>				8. UNIT or CA AGREEMENT NAME: Huntington CBM	
2. NAME OF OPERATOR: XTO Energy, Inc.				9. WELL NAME and NUMBER: State of Utah 17-8-21-33	
3. ADDRESS OF OPERATOR: 2700 Farmington Ave. B Farmington STATE NM ZIP 87401			PHONE NUMBER: (505) 324-1090		
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 2433' FSL x 1517' FEL AT PROPOSED PRODUCING ZONE: same				10. FIELD AND POOL, OR WILDCAT: Ferron Sandstone	
11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWSE 21 17S 8E S				12. COUNTY: Emery	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: Approximately 4.2 miles West of Huntington, Utah				13. STATE: UTAH	
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 400'		16. NUMBER OF ACRES IN LEASE: 1120		17. NUMBER OF ACRES ASSIGNED TO THIS WELL: 160	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) 7000'		19. PROPOSED DEPTH: 2,520		20. BOND DESCRIPTION: UTB-000138	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 6239' Ground Elevation		22. APPROXIMATE DATE WORK WILL START: 6/30/2006		23. ESTIMATED DURATION: 2 weeks	

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT	SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT
12.25"	8.625" J-55 24#	300	Class G 210+/- sacks 1.18 ft3/sx 15.7 ppg
7.875"	5.5" J-55 15.5#	2,520	CBM light wt - lead 230+/- sacks 4.14 ft3/sx 10.5 ppg
			Class G - tail 210+/- sacks 1.62 ft3/sx 14.2 ppg

ATTACHMENTS

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:

- | | |
|--|--|
| <input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER | <input checked="" type="checkbox"/> COMPLETE DRILLING PLAN |
| <input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER | <input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER |

NAME (PLEASE PRINT) <u>Kyla Vaughan</u>	TITLE <u>Regulatory Compliance Tech</u>
SIGNATURE <u><i>Kyla Vaughan</i></u>	DATE <u>4/10/2006</u>

(This space for State use only)

CC: SITLA

API NUMBER ASSIGNED: **43-015-38679**

APPROVAL:

RECEIVED
APR 13 2006

Range 8 East

(N89°53'E - 5248.32')

N89°35'23"E - 2633.16'

N89°34'41"E - 2614.82'

(N00°02'W - 2617.56')

(NORTH - 5487.90')

S00°14'49"E - 5272.86'

(N00°01'E)

3717.08'

21

1517.44'
CALCULATED

STATE OF UTAH
#17-8-21-33
ELEVATION 6239.1'

2432.99'
CALCULATED

UTM
N 4353061
E 497836

(N89°56'E - 5275.38')

Legend

- Drill Hole Location
- ⊕ Brass Cap (Found)
- Brass Cap (Searched for, but not found)
- △ Calculated Corner
- () GLO
- GPS Measured

NOTE:

UTM AND LATITUDE / LONGITUDE COORDINATES ARE DERIVED USING A GPS PATHFINDER AND ARE SHOWN IN NAD 27 DATUM.

LAT / LONG
39°19'43.828" N
111°01'30.398" W

Location:

THE WELL LOCATION WAS DETERMINED USING A TRIMBLE 4700 GPS SURVEY GRADE UNIT.

Basis of Bearing:

THE BASIS OF BEARING IS GPS MEASURED.

GLO Bearing:

THE BEARINGS INDICATED ARE PER THE RECORDED PLAT OBTAINED FROM THE U.S. LAND OFFICE.

Basis of Elevation:


BASIS OF ELEVATION OF 6495' BEING AT THE SOUTHEAST SECTION CORNER OF SECTION 20, TOWNSHIP 17 SOUTH, RANGE 8 EAST, SALT LAKE BASE & MERIDIAN, AS SHOWN ON THE RED POINT QUADRANGLE 7.5 MINUTE SERIES MAP.

Description of Location:

PROPOSED DRILL HOLE LOCATED IN THE NW 1/4 SE 1/4 OF SECTION 21; BEING 2862.23' SOUTH FROM THE NORTH LINE AND 3717.08' EAST FROM THE WEST LINE OF SECTION 21, T17S, R8E, SALT LAKE BASE AND MERIDIAN.

Surveyor's Certificate:

I, ALBERT J. SPENSKO, A REGISTERED PROFESSIONAL LAND SURVEYOR, HOLDING CERTIFICATE 146652 STATE OF UTAH, DO HEREBY CERTIFY THAT THE INFORMATION ON THIS DRAWING IS A TRUE AND ACCURATE SURVEY BASED ON DATA OF RECORD AND WAS CONDUCTED UNDER MY PERSONAL DIRECTION AND SUPERVISION AS SHOWN HEREON.



GRAPHIC SCALE

0 500' 1000'
(IN FEET)
1 inch = 1000 ft.



TALON RESOURCES, INC.

195 N. 100 W., P.O. Box 1230
Huntington, Utah 84528

Phone (435) 687-5310 Fax (435) 687-5311
E-Mail talon@etv.net



State of Utah #17-8-21-33
Section 21, T17S, R8E, S.L.B.&M.
Emery County, Utah

Drawn By: J. STANSFIELD	Checked By: L.W.J.
Drawing No. A-1	Date: 02/22/06
	Scale: 1" = 1000'
Sheet 1 of 4	Job No. 2057

Application for Permit to Drill Surface Use Plan

Company:

XTO Energy Inc.

Well No.

State of Utah 17-8-21-33

Location:

Sec. 21, T17S, R8E

State Lease No.

ML-48176

THIRTEEN POINT SURFACE USE PLAN

The dirt contractor will be provided with an approved copy of the surface use plan of operations before initiating construction.

1) Existing Roads:

- a) Proposed route to location: The proposed route to location is show on **Exhibit "A"** and is from the Red Point Quadrangle 7.5 minute series USGS quadrangle map
- b) Location of proposed well in relation to town or other reference point: The well is located approx. 4.2 miles west of Huntington, Utah. Go west on 4th north from Huntington 1.9 miles, turn left SW go 2.3 miles, turn left go .2 mile to location.
- c) Contact the County Road Department for use of county roads. The use of Emery County roads will require an encroachment permit from the Emery County Road Department. No encroachment permit will be required.
- d) Plans for improvement and/or maintenance of existing roads: All existing roads within 1 mile of the drill site are shown on **Exhibit "B"**. All existing roads that will be used to the well location will be maintained to their current conditions or better.
- e) Other: None

2) Planned Access Roads:

- a) Location (centerline): Starting from a point along an existing road in the SE/4 of Section 21, T17S, R8E.
- b) Length of new access top be constructed: Approximately 1,405 feet of new access road will be constructed in order to gain safe access to the well pad. **See Exhibit "B"**.
- c) Length of existing roads to be upgraded: No additional upgrades should be necessary to existing roads
- d) Maximum total disturbed width: Typically new access roads require up to 60' of disturbed width which includes ROW for gas and water pipe lines and electric service.
- e) Maximum travel surface width: 25' or less
- f) Maximum grades: Maximum grades will not exceed 10% after construction.
- g) Turnouts: No turnouts are planned at this time.
- h) Surface materials: Only native materials will be used if additional construction is required. If necessary, gravel or rock maybe purchased and used to improve road conditions and travel.

- i) Drainage (crowning, ditching, culverts, etc): Roads will be re-crowned and bar ditches, if necessary, will be located along either side. 18"-24" culverts will be installed as necessary.
- j) Cattle guards: No cattle guards are planned at this time. If necessary cattle guards will be specified in the stipulations.
- k) Length of new and/or existing roads which lie outside the lease or unit boundary for which a BLM/state/fee right-of-way is required: None
- l) Other:
 - i) Surface disturbance and vehicular travel will be limited to the approved location and access road. Any additional area needed must be approved by the State of Utah in advance.
 - ii) If a right-of-way is necessary, no surface disturbing activities shall take place on the subject right-of-way until the associated APD is approved. The holder will adhere to conditions of approval in the Surface Use Program of the approved APD, relevant to any right-of-way facilities.
 - iii) If a right-of-way is secured, boundary adjustments in the lease or unit shall automatically amend this right-of-way to include that portion of the facility no longer contained within the lease or unit. In the event of an automatic amendment to this right-of-way grant, the prior on-lease/unit conditions of approval of this facility will not be affected even though they would now apply to facilities outside of the lease/unit as a result of a boundary adjustment. Rental fees, if appropriate shall be recalculated based on the conditions of this grant and the regulations in effect at the time of an automatic amendment.
 - iv) If at any time the facilities located on public lands authorized by the terms of the lease are no longer included in the lease (due to a contraction in the unit or other lease or unit boundary change) the State of Utah will process a change in authorization to the appropriate statute. The authorization will be subject to appropriate rental, or other financial obligations determined by the State of Utah.
 - v) If the well is not productive, the access road will be rehabilitated or brought to Resource (Class III) Road Standards within 60 days of dismantling the rig. If upgraded, the access road must be maintained at these standards until the well is properly abandoned. If this time frame cannot be met, the Field Office Manager will be notified so that temporary drainage control can be installed along the access road.
- 3) Location of Existing Wells -on a map, show the location of all water, injection, disposal, producing and drilling wells within a one mile radius of the proposed well, and describe the status of each: **See Exhibit "C"**.
- 4) Location of Production Facilities:
 - a) On-site facilities: Typical on-site facilities will consist of a wellhead, gas flow line, water flow line, artificial lifting system (pumping unit), 2 phase separator, gas measurement, water measurement, electronics, a heated enclosure/building for weather and environmental protection and chemical injection equipment (as required). All production and measurement shall conform to the provisions of 43 CFR § 3162.7 and Onshore Oil and Gas Order No. 4, if applicable.
 - b) All permanent (in place for six months or longer) structures constructed or installed on the well site location will be painted a flat, non reflective color to match the standard environmental colors, as specified by the COA's in the APD. All facilities will be painted within six months of installation. Facilities required complying with the Occupational Safety and Health Act (OSHA) may be excluded.

- c) Off-site facilities: Off-site facilities are located at the CDP station and include compression, processing, separation, tanks, pits, electronics and produced water disposal (SWD) well.
 - d) Pipelines: The well will be produced into gas and water pipelines (sizes to be determined) and transported to existing pipelines. **See Exhibit "B"** for the proposed pipe line route.
 - e) Power lines: Power lines are located underground in the same ROW as the water and gas pipe lines.
- 5) Location and Type of Water Supply:
- a) All water needed for drilling purposes will be obtained from (describe location and/or show on a map): All water required for drilling will be purchased from a local municipal water supply. If possible, currently produced coal well water may also be used after receiving any necessary permits. Water will be trucked to location by a third party trucking company who specializes in water hauling.
 - b) Water obtained on private land, or land administered by another agency, will require approval from the owner or agency for use of the land.
- 6) Source of Construction Material:
- a) Pad construction material will be obtained from (if the source is Federally owned, show location on a map): All construction material will be purchased from private landowners or a commercial gravel/materials pit. The use of materials will conform to 43 CFR § 3610.2-3, if applicable.
 - b) The use of materials under State of Utah jurisdiction will conform to 43 CFR § 3610.2-3, if applicable.
- 7) Methods of Handling Waste Disposal:
- a) Describe the methods and locations proposed for safe containment and disposal of waste material, e.g. cuttings, produced water, garbage, sewage, chemicals, etc. The reserve pit will be located along the edge and within the boundaries of the designated well pad. The walls of the pit will be sloped at no greater than 2 to 1 and will be lined with a synthetic material of approximately 12 mils in thickness. The reserve pit shall be located in cut material, with at least 50% of the pit volume being below original ground level. Three sides of the pit will be fenced before drilling starts. The fourth side will be fenced as soon as drilling is completed, and shall remain until the pit is dry. The amount of time the pit may remain open will typically be specified by the COA's. Once dry, the liner will be cut and removed at the mud line and the pit will be covered and buried in place.
 - b) Trash must be contained in a trash cage and hauled away to an approved disposal site as necessary but no later than at the completion of drilling operations.
 - c) Sewage from trailers and chemical portable toilets will be removed on a regular basis by a third party contractor and disposed of at an authorized sanitary waste facility.
 - d) Any and all chemicals used during the drilling and completion of the well will be kept to a minimum and stored within the boundaries of the well pad. The third party chemical contractor will be responsible for containment and clean-up and removal of all spilled chemicals on location.
- 8) Ancillary Facilities: No ancillary facilities will be required during the drilling or completion of the well.
- 9) Well Site Layout -depict the pit, rig, cut and fill, topsoil, etc. on a plat with a scale of at least 1"=50'. **See Exhibit "D" & "E"**.

- a) All equipment and vehicles that will be used to drill and complete this well will remain within the boundaries of the approved wellpad. Any equipment and or vehicles park or stored off of the location will be considered trespassing on federal lands and will NOT be tolerated.
- b) Materials obtained from the construction of location, like topsoil and vegetation will be stock piled as indicated and permitted by the approved APD. The stock piles themselves may be outside the approved boundaries of the well pad.

10) Plans for Restoration of the Surface:

- a) The top 6 inches of topsoil material will be removed from the location and stockpiled separately on: Adjacent Land or as specified by the approved APD.
- b) Topsoil along the access road will be reserved in place adjacent to the road.
- c) Within 30-45 days after completion of well, all equipment that is not necessary for production shall be removed.
- d) The reserve pit and that portion of the location not needed for production will be reclaimed 90-120 days after completion of the well.
- e) Before any dirt work to restore the location takes place, the reserve pit must be ready for burial.
- f) All road surfacing will be removed prior to the rehabilitation of roads.
- g) Reclaimed roads will have the berms and cuts reduced and will be closed to vehicle use.
- h) All disturbed areas will be re-contoured to replicate the natural slope.
- i) The stockpiled topsoil will be evenly distributed over the disturbed area.
- j) Prior to reseeding, all disturbed areas, including the access roads, will be scarified and left with a rough surface.
- k) Seed will be broadcast or drilled between September and November, or at a time specified by the BLM and or state. If broadcast, a harrow or some other implement will be dragged over the seeded area to assure seed coverage.
- l) The following seed mixture will be used: As specified in the conditions of approval
- m) If necessary, an abandonment marker will be one of the following, as specified by the State of Utah:
 - i) at least four feet above ground level,
 - ii) at restored ground level, or
 - iii) below ground level.
 - iv) In any case the marker shall be inscribed with the following: operator name, lease number, well name and surveyed description (township, range, section and either quarter-quarter or footages).

n) Additional requirements: None

11) Surface and Mineral Ownership: Both the surface and minerals are owned by the State of Utah.

12) Other Information:

- a) Archeological Concerns: An approved contractor will submit the appropriate reports to the agency as required. Special stipulations will be included in the COA's of the approved APD.
- b) The operator is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator is to immediately stop work that might further disturb such materials, and contact the State of Utah Field Office. Within five (5) working days, the State of Utah will inform the operator as to:
 - i) whether the materials appear eligible for the National Register of Historic Places;
 - ii) the mitigation measures the operator will likely have to undertake before the site can be used (assuming in situ preservation is not necessary); and
 - iii) a time frame for the State of Utah to complete an expedited review under 36 CFR § 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the State of Utah are correct and that mitigation is appropriate.
- c) If the operator wishes, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the State of Utah will assume responsibility for whatever recordation and stabilization of the exposed materials may be required. Otherwise, the operator will be responsible for mitigation costs. The State of Utah will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the State of Utah that the required mitigation has been completed, the operator will then be allowed to resume construction.
- d) Threatened and Endangered Species Concerns: An approved contractor will submit the appropriate reports as required. Special stipulation will be included in the COA's of the approved APD.
- e) Wildlife Seasonal Restrictions: Current wildlife restrictions and closure dates are specified in the BLM's Environmental Impact Statement.

13) The Drilling Program is attached: **See Exhibit "F"**.

14) Lessee's or Operator's Representatives and Certification:

Permitting & Compliance:

Kyla Vaughan
Regulatory Compliance
XTO Energy Inc.
2700 Farmington Avenue, Bldg K, Suite 1
Farmington NM 87401
505-324-1090


Drilling & Completions:

Greg Vick
Drilling Engineer
XTO Energy Inc.
2700 Farmington Avenue, Bldg K, Suite 1
Farmington NM 87401
505-324-1090


Certification:


I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which currently exist; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by **XTO Energy Inc.** and its contractors and subcontractors in conformity with this APD package and the terms and conditions under which it is approved. I also certify responsibility for the operations conducted on that portion of the leased lands associated with this application, with bond coverage being provided by **XTO Energy Inc.** This statement is subject to the provisions of 18 U.S.C. § 1001 for the filing of a false statement.

Signature




Date








TN/MN
12x°

EXHIBIT A



ELEVATION OF UNGRADED GROUND AT LOCATION STAKE = 6239.1'
 ELEVATION OF GRADED GROUND AT LOCATION STAKE = 6238.6'




TALON RESOURCES, INC.
 195 North 100 West P.O. Box 1230
 Huntington, Utah 84528
 Phone (435)687-5310 Fax (435)687-5311
 E-Mail talon@etv.net




LOCATION LAYOUT
 Section 21, T17S, R8E, S.L.B.&M.
 State of Utah #17-8-21-33

Drawn By: J. STANSFIELD	Checked By: L.W.J.
Drawing No. A-2	Date: 01/30/06
	Scale: 1" = 50'
Sheet 2 of 4	Job No. 2057

EXHIBIT D



1" = 10'
X-Section
Scale
1" = 40'



SLOPE = 1 1/2 : 1
(EXCEPT PIT)
PIT SLOPE = 1 ; 1



TALON RESOURCES, INC.

195 North 100 West P.O. Box 1230
Huntington, Utah 84528

Phone (435)687-5310 Fax (435)687-5311
E-Mail talon@etv.net



TYPICAL CROSS SECTION
Section 21, T17S, R8E, S.L.B.&M.
State of Utah #17-8-21-33

Drawn By: J. STANSFIELD	Checked By: L.W.J.
Drawing No. C-1	Date: 01/30/06
	Scale: 1" = 40'
Sheet 3 of 4	Job No. 2057

APPROXIMATE YARDAGES

CUT

(6") TOPSOIL STRIPPING = 750 CU. YDS.

REMAINING LOCATION = 2,450 CU. YDS.

TOTAL CUT = 3,910 CU. YDS.

TOTAL FILL = 2,350 CU. YDS.

XTO ENERGY INC.
State of Utah 17-8-21-33
Drilling Data for APD
April 5, 2006

Location: 2433' FSL & 1517' FEL, Sec 21, T17S, R 8E

Projected TD: 2,520'
Approximate Elevation: 6,239'

Objective: Ferron Coal/Sand
KB Elevation: 6,251'

1) Mud Program:

INTERVAL	0' to 300'	300' to 2520'
HOLE SIZE	12.25"	7.875"
MUD TYPE	Air Drill	Air/LSND / Gel Chemical
WEIGHT	N/A	8.4 - 8.6
VISCOSITY	N/A	45 - 60
WATER LOSS	N/A	8 - 10

- a) Air drill to TD unless excessive water flow is encountered then switch to water based mud. If mud is required, use fibrous materials as needed to control seepage and lost circulation. Pump high viscosity sweeps as needed for hole cleaning. Raise viscosity at TD for logging. Reduce viscosity after logging for cementing.
- b) The blooie line will be approximately 100' in length and will extend in a straight line from below the rotating head as indicated in the BOP schematic. An automatic spark-type igniter will be fixed to the end of the blooie line and set to provide a continuous spark to ignite and burn any produced hydrocarbons and/or gases.
- c) If necessary, de-dusting will be accomplished with a small pump, waterline and spray nipple positioned near the end of the blooie line to provide a continuous spray of water.
- d) Sufficient mud materials will be stored on location to maintain well control and combat lost circulation problems that might reasonably be expected.
- e) The BOP system will be consistent with API RP 53 and Onshore Oil and Gas Order No. 2. Pressure tests of the surface casing and all BOP equipment subject to pressure will be conducted before drilling the surface casing shoe. Blowout preventer controls will be installed prior to drilling the surface casing shoe and will remain in use until the well is completed or abandoned. Ram preventers shall be inspected and operated daily. Annular preventers shall be inspected and operated weekly to ensure good mechanical working order. The inspections and tests shall be recorded in the drilling log and daily drilling report. See the attached BOP and choke manifold schematic.

2) Casing Program:

Length	Weight	Grade	Coll Pressure	Burst Pressure	Joint Strength	ID	Drift	SF Collapse	SF Burst	SF Tension
8.625 in, ST&C surface casing set in a 12.25 in hole										
300	24	J-55	950	2,950	272	8.097	7.97	7.30	22.66	37.78
5.5 in, ST&C production casing set in a 7.875 in. hole										
2,520	15.5	J-55	4,040	4,810	202	4.95	4.83	3.69	4.40	5.17

EXHIBIT F

3) Well Heads:

- a) Casing Head: Install Larkin Fig 92 (or equivalent), 10" nominal, 2,000 psig WP (4,000 psig test) with 8-5/8" 8rnd thread on bottom and 10-3/4" 8rnd thread on top. NU BOP and choke manifold (see attached schematic). Stack to consist of drilling spool with choke and kill lines, double rams with pipe rams on top, blind rams on bottom. Use cold water and test BOP to 250 psi low and 1,000 psi high. Record all tests on the IADC report. Inspect accumulator and closing unit to ensure that pre-charge pressures and oil levels are within API Specifications and report same on IADC report.
- b) Tubing Head: Larkin Fig 612 (or equivalent), 5,000 psig WP (5,000 psig test), 5-1/2" SOW (or 8rnd female thread) on bottom, 7-1/16" 5,000# flange on top w/2 - 3" LPOs.

4) Cement Program: Slurry design may change slightly, but design is to circulate cement to surface on both casing strings.

- a) Surface: 210 sx of Class G cement (or equivalent) containing 2% KCl, 1/4 % Flocele and dispersant mixed at 15.7 ppg & 1.18 ft³/sk.

- i) Slurry volume is 290 ft³, 200% excess of calculated annular volume to 300'.

- b) Production:

- i) Lead Cement: 230 sx of CBM Light Weight Cement with 10 pps Gilsonite and 1/4 pps celloflake mixed at 10.5 ppg and 4.14 ft³/sk.

- ii) Tail Cement: 210 sx of Class G (or equivalent) with 10% Cal-Seal, 1/4 pps celloflake and dispersant mixed at 14.2 ppg and 1.62 ft³/sk.

- iii) The Production Casing will be cemented using 2 (lead and tail) cement slurries. The lead cement (filler grade) volume will be calculated from 500' above the Upper Ferron Sandstone to surface. The Tail Cement will be calculated from TD to 500' above the Upper Ferron Sandstone as indicated on the formation tops table.

- (1) Slurry volume is 1,290 ft³, 200% excess of calculated annular volume to 3,683'.

- c) Slurry designs may change based upon actual conditions. Final cement volumes will be determined from caliper logs plus 100%.

5) Logging Program

- a) Mud Logger: The mud logger will come on at 300' and will remain on the hole until TD. The mud will be logged in 10' intervals.
- b) Open Hole Logs as follows: Run Array Induction (if wet), compensated neutron, density, GR, caliper, SP (if wet) and Pe fr/TD to the bottom of the surface csg.

6) Formation Tops:

Formation	Sub-Sea	Well Depth
Top Upper Ferron Sand	4,105	2,115
Top of Ferron Coal Zone	3,955	2,265
Top of Lower Ferron Sand	3,900	2,320
TOTAL DEPTH		2,620

- a) No known oil zones will be penetrated.
- b) Gas bearing sandstones and coals will be penetrated from 3,218' to 3,383'.

- c) No known water zones will be penetrated. The gas bearing sandstones and coals may contain in-situ water.
- d) No known mineral zones will be penetrated.
- e) Any prospectively valuable minerals and all fresh water zones encountered during drilling will be recorded and cased and cemented. If possible, water flow rates will be measure and samples will be taken and analyzed with the results being submitted to the State of Utah.

7) Company Personnel:

Name	Title	Office Phone	Home Phone
Greg Vick	Drilling Engineer	505-566-7946	505-320-7274
Jerry Lacy	Drilling Super.	505-566-7914	505-320-6543
Dennis Elrod	Drilling Foreman	505-566-7907	505-486-6460
Joshua Stark	Project Geologist	817-885-2240	817-565-7158
Jerry Stadulis	Reservoir Engineer	817-855-2338	817-480-4056

BOP SCHEMATIC FOR DRILLING OPERATIONS CLASS 1 (2M) NORMAL PRESSURE

TESTING PROCEDURE

1. Test BOP & r installation:

Pressure test BOP to 200-300
psig (low pressure) for 10 min.

Test BOP to Working Press or
to 70% internal yield of surf csg
(10 min) or which ever is less.


2. Test operation of (both) rams on every trip.

3. Check and record Accumulator pressure on every tour.

4. Re-pressure test BOP stack after changing out rams.

5. Have kelly cock valve with handle available.


6. Have safety valve and subs to fit all sizes of drill string on the rig floor and ready to go.



CHOKE MANIFOLD SCHEMATIC FOR DRILLING OPERATIONS CLASS 1 (2M) NORMAL PRESSURE

1. Stake all lines from choke manifold to pit.
2. Pressure test choke manifold after installation.
3. Pressure test manifold at the same time with the BOP Stack. Test manifold to the same test pressures.

TESTING PROCEDURE



WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 04/13/2006

API NO. ASSIGNED: 43-015-30679

WELL NAME: ST OF UT 17-8-21-33

OPERATOR: XTO ENERGY INC (N2615)

CONTACT: KYLA VAUGHAN

PHONE NUMBER: 505-324-1090

PROPOSED LOCATION:

NWSE 21 170S 080E

SURFACE: 2433 FSL 1517 FEL

BOTTOM: 2433 FSL 1517 FEL

COUNTY: EMERY

LATITUDE: 39.32882 LONGITUDE: -110.0250

UTM SURF EASTINGS: 497846 NORTHINGS: 4353059

FIELD NAME: BUZZARD BENCH (132)

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering	DUD	5/15/06
Geology		
Surface		

LEASE TYPE: 3 - State

LEASE NUMBER: ML-48176

SURFACE OWNER: 3 - State

PROPOSED FORMATION: FRSD

COALBED METHANE WELL? ☒

RECEIVED AND/OR REVIEWED:

☒ Plat
☒ Bond: Fed[] Ind[] Sta[] Fee[]
(No. 104312762)
☒ Potash (Y/N)
☒ Oil Shale 190-5 (B) or 190-3 or 190-13
☒ Water Permit
(No. MUNICIPAL)
☒ RDCC Review (Y/N)
(Date: _____)
☒ Fee Surf Agreement (Y/N)
☒ Intent to Commingle (Y/N)

LOCATION AND SITING:


____ R649-2-3.
Unit: HUNTINGTON CBM ☒
____ R649-3-2. General
Siting: 460 From Qtr/Qtr & 920' Between Wells
____ R649-3-3. Exception
☒ Drilling Unit
Board Cause No: 245-2
Eff Date: 4-25-01
Siting: Suspension from Drilling
____ R649-3-11. Directional Drill

COMMENTS:

Needs Perm (04-28-06)

STIPULATIONS:

1- STATEMENT OF BASIS



OPERATOR: XTO ENERGY INC (N2615)

SEC: 21,22,28 T. 17S R. 8E

FIELD: BUZZARD BENCH (132)

COUNTY: EMERY

CAUSE: 245-2 / 4-25-2001

Field Status


- ABANDONED
- ACTIVE
- COMBINED
- INACTIVE
- PROPOSED
- STORAGE
- TERMINATED

Unit Status

- EXPLORATORY
- GAS STORAGE
- NF PP OIL
- NF SECONDARY
- PENDING
- PI OIL
- PP GAS
- PP GEOTHERML
- PP OIL
- SECONDARY
- TERMINATED

Wells Status

- GAS INJECTION
- GAS STORAGE
- LOCATION ABANDONED
- NEW LOCATION
- PLUGGED & ABANDONED
- PRODUCING GAS
- PRODUCING OIL
- SHUT-IN GAS
- SHUT-IN OIL
- TEMP. ABANDONED
- TEST WELL
- WATER INJECTION
- WATER SUPPLY
- WATER DISPOSAL
- DRILLING



Utah Oil Gas and Mining



PREPARED BY: DIANA WHITNEY
DATE: 13-APRIL-2006

**DIVISION OF OIL, GAS AND MINING
APPLICATION FOR PERMIT TO DRILL
STATEMENT OF BASIS**

OPERATOR: XTO Energy Inc.

WELL NAME & NUMBER: State of Utah 17-8-21-33

API NUMBER: 43-015-30679

LOCATION: 1/4,1/4 NWSE Sec: 21 TWP: 17 S RNG: 8 E 2433 FSL 1517 FEL

Geology/Ground Water:

The well will spud into a poorly to moderately permeable soil that is developed on the Lower unit of the Emery Sandstone Member of the Mancos Shale. Local outcrops dip into the Wasatch Plateau at about 5° to the northwest. No aquifers with high quality ground water are likely to be encountered below the Lower unit of the Emery Sandstone. The proposed surface casing and cementing program should ensure the protection of any unknown near surface ground water resources. A search of the Division of Water Rights records indicates that no water rights have been filed on subsurface water within a mile of the location.

Reviewer: Christopher J. Kierst

Date: May 8, 2006

Surface:

On-site conducted April 27, 2006. In attendance: Bart Kettle (DOGM), Tony Wright (DWR), Ray Trujillo (XTO), Allen Childs (Talon), Ray Peterson (Emery County) and Bedos (Nelsons Construction) invited but choosing not to attend Jim Davis (SITLA), Ed Bonner (SITLA).

Emery County recommends that XTO work with the grazing permit holders on fence crossings.

Reviewer: Bart T Kettle

Date: 04/28/06

Conditions of Approval/Application for Permit to Drill:

- 1.
- 2.
- 3.
- 4.
- 5.
- 6.
- 7.

ON-SITE PREDRILL EVALUATION
Division of Oil, Gas and Mining

OPERATOR: XTO Energy Inc.

WELL NAME & NUMBER: State of Utah 17-8-21-33

API NUMBER: 43-015-30679

LEASE: State **FIELD/UNIT:** Huntington CBM

LOCATION: 1/4, 1/4 NWSE **Sec:** 21 **TWP:** 17 S **RNG:** 8 E 2433 FSL 1517 FEL

LEGAL WELL SITING: General Statewide Siting suspended.

GPS COORD (UTM): X = E; Y = N **SURFACE OWNER:** SITLA

PARTICIPANTS

Bart Kettle (DOGM), Allen Childs (Talon Resources Inc), Ray Trujillo (XTO), Tony Wright (DWR), Ray Peterson (Emery County) and Bedos (Nelsons Construction). Invited but choosing not to attend Jim Davis (SITLA) and Ed Bonner (SITLA).

REGIONAL/LOCAL SETTING & TOPOGRAPHY

Proposed project is ~4.2 miles west of Huntington, located in Emery County Utah. Location is surrounded by rangelands with many steep gullies and dry wash's cutting through a series of mesas rising to the east. Drainages flow into Huntington Creek within five miles and eventually to the Green River 60 miles away. The project is located in a 10-12" precept zone at the base of the eastern portion of the Wasatch Plateau. Agriculture lands are located along the valley floor to the east. With the exception of patchy agriculture lands to the east and montane forest of the Wasatch Plateau the regional topography is arid rangelands dominated by Salt Scrub shrublands and Pinion/Juniper woodlands. Soils in the region are generally poorly developed, and moderate to highly erosive. There were no perennial streams or springs observed in close proximity to the location. Drainages in the immediate area are dry washes, flowing water during the extreme rain events of the monsoon season and during spring snow melt.

SURFACE USE PLAN

CURRENT SURFACE USE: Seasonal livestock grazing, late winter/spring big game range, wildlife habitat, and OHV recreational use.

PROPOSED SURFACE DISTURBANCE: 1405' of new road with a 25' running surface will be constructed. Well pad 260'x126'

LOCATION OF EXISTING WELLS WITHIN A 1 MILE RADIUS: Three existing wells, two proposed.

LOCATION OF PRODUCTION FACILITIES AND PIPELINES: Facilities consisting of a wellhead, flowlines, lifting system, separator measurement equipment and enclosed building for measurement equipment will be located on-site. A pipeline for transport of produced gas and water will run from this well and tie into an existing line along the access road.

SOURCE OF CONSTRUCTION MATERIAL: On location or local sources.

ANCILLARY FACILITIES: None

WILL DRILLING AT THIS LOCATION GENERATE PUBLIC INTEREST OR CONCERNS: Limited public interest or concern is anticipated during drilling and production of this well.

WASTE MANAGEMENT PLAN:

Reserve pit will be lined and fenced to allow fluids too evaporate. Once dry the reserve pit contents will be buried in place, back fill will be sufficiently deep so that no liner is exposed. Trash must be contained in a trash cage and hauled away to an approved disposal site as necessary but no later than at the completion of drilling operations.

ENVIRONMENTAL PARAMETERS

AFFECTED FLOODPLAINS AND/OR WETLANDS: Dry washes, no live water was observed in close proximity to the well pad or access road.

FLORA/FAUNA: Mule Deer, Elk, Blacktail jackrabbits, raptors, rodents and lizards.

Grasses: Curly galleta, bottlebrush squirrel tail, Salina wild ryegrass, and Indian ricegrass. Shrubs: Utah serviceberry, black sage, shadscale saltbrush, mat saltbrush, broom snake weed, birch leaf mountain mahogany, grease brush, Mormon tea, and buckwheat. Trees: Utah Juniper and Two Needle pinyon pine. Forbs: Vetch spp, Indian paint brush, bur buttercup, Russian thistle, purple mustard, Palmers penstemon, hairy aster, pepper weed, and spring parsley. Other: None noted.

SOIL TYPE AND CHARACTERISTICS: Clay loam dominated with some sandy clays.

SURFACE FORMATION & CHARACTERISTICS: Blue Gate Member of the Mancos Shale/clay and alluvial outwash. Soils at the well site are erosive in nature and are very fine clays.

EROSION/SEDIMENTATION/STABILITY: Most of the project area lays in areas of clay loam soils ranging from high to moderate potential for wind erosion. The project area has moderate water erosion potential. Soil erosion would increase during the initial construction phase of the project. Removal of vegetation and physical soil crust will reduce surface soil aggregates and therefore reduce soil stability. Loose unstable berms of soil will be left along the roadside and water runoff patterns will be re-directed. These factors will contribute to increased potential for wind and water erosion. As vegetation and soil crusts recover along the roadway soils will become more stable. Wind and water erosion rates would be partially reduced, but still accelerated from normal rates.

PALEONTOLOGICAL POTENTIAL: None noted

RESERVE PIT

CHARACTERISTICS: 100'x44'x12'

LINER REQUIREMENTS (Site Ranking Form attached): Lining is optional.

SURFACE RESTORATION/RECLAMATION PLAN

Well site and immediate area will be cleared of debris and material not needed for production after the completion of drilling. Reclamation will start within 120 days of the completion of the well. Areas not required for production will be reclaimed. Reclaimed portions of the well pad will be seeded in late fall or winter with seed mixture specified by the State of Utah.

SURFACE AGREEMENT: As per SITLA mineral lease.

CULTURAL RESOURCES/ARCHAEOLOGY: On file

OTHER OBSERVATIONS/COMMENTS

DWR provided no comments or recommendations. Emery County recommended that TXO work with the grazing permit holder on fence crossings.

ATTACHMENTS

Photos of this location were taken and placed on file.

Bart Kettle
DOGM REPRESENTATIVE

04/28/2006 10:36 a.m.
DATE/TIME

**Evaluation Ranking Criteria and Ranking Score
For Reserve and Onsite Pit Liner Requirements**

<u>Site-Specific Factors</u>	<u>Ranking</u>	<u>Site Ranking</u>
Distance to Groundwater (feet)		
>200	0	
100 to 200	5	
75 to 100	10	
25 to 75	15	
<25 or recharge area	20	<u>0</u>
Distance to Surf. Water (feet)		
>1000	0	
300 to 1000	2	
200 to 300	10	
100 to 200	15	
< 100	20	<u>0</u>
Distance to Nearest Municipal Well (feet)		
>5280	0	
1320 to 5280	5	
500 to 1320	10	
<500	20	<u>0</u>
Distance to Other Wells (feet)		
>1320	0	
300 to 1320	10	
<300	20	<u>0</u>
Native Soil Type		
Low permeability	0	
Mod. permeability	10	
High permeability	20	<u>0</u>
Fluid Type		
Air/mist	0	
Fresh Water	5	
TDS >5000 and <10000	10	
TDS >10000 or Oil Base Mud Fluid	15	
containing significant levels of hazardous constituents	20	<u>0</u>
Drill Cuttings		
Normal Rock	0	
Salt or detrimental	10	<u>0</u>
Annual Precipitation (inches)		
<10	0	
10 to 20	5	
>20	10	<u>5</u>
Affected Populations		
<10	0	
10 to 30	6	
30 to 50	8	
>50	10	<u>0</u>
Presence of Nearby Utility Conduits		
Not Present	0	
Unknown	10	
Present	15	<u>0</u>

Final Score 5 (Level III Sensitivity)

Sensitivity Level I = 20 or more; total containment is required, consider criteria for excluding pit use.

Sensitivity Level II = 15-19; lining is discretionary.

Sensitivity Level III = below 15; no specific lining is required.

Criteria for determining when to exclude or discourage the use of reserve pits on a proposed drilling location

1. Proposed well location is situated near a surface water source or drainage, such that a breach of a pit would result in fluid entering surface waters.
2. Proposed well location is built on materials such that a breach of a pit would result in fluid entering shallow ground water, and/or could be conducted to nearby surface waters.

Example of 1)

Pit would be located above a stream such that any loss of fluid to the location surface would drain naturally to the stream, and strata beneath the pit is fractured or otherwise permeable such that a leak from the pit would result in fluid entering the stream or drainages leading directly to the stream.

Example of 2)

Pit would be located on the flood plain of a stream such that any loss of fluid to the surface, or from a pit leak, would flow through permeable near surface materials directly to the nearby stream.

It is unlawful for any person to discharge a pollutant into "Waters of the State" or to place or cause to be placed any wastes in a location where there is probable cause to believe it will cause pollution. Discharge of pollutants into surface waters must be covered under a UPDES or NPDES permit or could be subject to penalties under the Utah Water Quality Act or Federal Clean Water Act. Waters of the State is broadly defined and includes all surface and ground waters (not confined and retained within private property limits) and drainage systems.

Alternatives to consider:

1. Use a closed mud system.
2. Move the location.
3. Directional drill.



[State Online Services](#)

[Agency List](#)

[Business.utah.gov](#)

Search Utah.gov



UTAH DIVISION OF WATER RIGHTS

Sorry. No diversion points. Try browsing!

[Natural Resources](#) | [Contact](#) | [Disclaimer](#) | [Privacy Policy](#) | [Accessibility Policy](#)

05-06 XTO St of UT 17-8-21-33

Casing Schematic

Manos Scale

Surface

TOC @
0.

TOC @
0.

8-5/8"
MW 8.4
Frac 19.3

Surface
300. MD

✓ 6 1/8" casing

PSH

$$(.052)(.2520)(8.6) = 1126$$

Gas

$$(.10)/(.2520) = .2952$$

11154' 874

Boil 20,000 ✓

1408
Too Fast

Gas Csg = .2952
v 2.2% = .0065

✓ 6 1/8" casing

Max pressure @ Gas Csg shoe (638)
Test to 638 ✓

2115
Too Fast

✓ Adequate OK 5/15/06

5-1/2"
MW 8.6

Production
2520. MD

Well name:

05-06 XTO St of UT 17-8-21-33

Operator: XTO Energy Inc

String type: Surface

Project ID:

43-015-30679

Location: Emery County

Design parameters:**Collapse**

Mud weight: 8.400 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 79 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 299 ft

Cement top: Surface

Burst

Max anticipated surface pressure: 264 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 300 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on buoyed weight.

Neutral point: 262 ft

Non-directional string.

Re subsequent strings:

Next setting depth: 2,520 ft
Next mud weight: 8.600 ppg
Next setting BHP: 1,126 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 300 ft
Injection pressure 300 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	300	8.625	24.00	J-55	ST&C	300	300	7.972	14.4
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	131	1370	10.465	300	2950	9.83	6	244	38.78 J

Prepared by: Clinton Dworshak
Utah Div. of Oil & Mining

Phone: 801-538-5280
FAX: 801-359-3940

Date: May 10, 2006
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 300 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

Well name:

05-06 XTO St of UT 17-8-21-33

Operator: **XTO Energy Inc**

String type: Production

Project ID:

43-015-30679

Location: Emery County

Design parameters:**Collapse**Mud weight: 8.600 ppg
Design is based on evacuated pipe.**Minimum design factors:****Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 110 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,500 ft

Cement top: Surface

BurstMax anticipated surface
pressure: 253 psi
Internal gradient: 0.346 psi/ft
Calculated BHP 1,126 psi

No backup mud specified.

Tension:8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Non-directional string.

Tension is based on buoyed weight.

Neutral point: 2,192 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	2520	5.5	15.50	J-55	ST&C	2520	2520	4.825	79
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	1126	4040	3.588	1126	4810	4.27	34	202	5.95 J

Prepared Clinton Dworshak
by: Utah Div. of Oil & MiningPhone: 801-538-5280
FAX: 801-359-3940Date: May 10, 2006
Salt Lake City, Utah**Remarks:**Collapse is based on a vertical depth of 2520 ft, a mud weight of 8.6 ppg. The casing is considered to be evacuated for collapse purposes.
Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.



State of Utah

Department of Natural Resources

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas & Mining

JOHN R. BAZA
Division Director

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

May 16, 2006

XTO Energy, Inc.
2700 Farmington Ave. Bldg. K, Ste. 1
Farmington, NM 87401

Re: State of Utah 17-8-21-33 Well, 2433' FSL, 1517' FEL, NW SE, Sec. 21,
T. 17 South, R. 8 East, Emery County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-015-30679.

Sincerely,

A handwritten signature in black ink, appearing to read "Gil Hunt".

Gil Hunt
Associate Director

pab
Enclosures

cc: Emery County Assessor
SITLA
Bureau of Land Management, Moab District Office

Operator: XTO Energy, Inc.
Well Name & Number State of Utah 17-8-21-33
API Number: 43-015-30679
Lease: ML-48176

Location: NW SE **Sec.** 21 **T.** 17 South **R.** 8 East

Conditions of Approval

1. **General**

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for Permit to Drill.

2. **Notification Requirements**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- 24 hours prior to cementing or testing casing
- 24 hours prior to testing blowout prevention equipment
- 24 hours prior to spudding the well
- within 24 hours of any emergency changes made to the approved drilling program
- prior to commencing operations to plug and abandon the well

The following are Division of Oil, Gas and Mining contacts and their work telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at (801) 538-5338
- Carol Daniels at (801) 538-5284 (spud)

3. **Reporting Requirements**

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations, you are required to immediately suspend all operations and immediately inform the Trust Lands Administration and the Division of State History of the discovery of such remains.

5. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐
(highlight changes)

APPLICATION FOR PERMIT TO DRILL		5. MINERAL LEASE NO: ML-48176	6. SURFACE: State
1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>		7. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A	
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/>		8. UNIT or CA AGREEMENT NAME: Huntington CBM	
2. NAME OF OPERATOR: XTO Energy, Inc.		9. WELL NAME and NUMBER: State of Utah 17-8-21-33	
3. ADDRESS OF OPERATOR: 2700 Farmington Ave. B Farmington STATE NM ZIP 87401		10. FIELD AND POOL, OR WILDCAT: Ferron Sandstone	
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 2433' FSL x 1517' FEL AT PROPOSED PRODUCING ZONE: same		11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWSE 21 17S 8E S	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: Approximately 4.2 miles West of Huntington, Utah		12. COUNTY: Emery	13. STATE: UTAH
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 400'	16. NUMBER OF ACRES IN LEASE: 1120	17. NUMBER OF ACRES ASSIGNED TO THIS WELL: 160	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) 7000'	19. PROPOSED DEPTH: 2,520	20. BOND DESCRIPTION: UTB-000138	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 6239' Ground Elevation	22. APPROXIMATE DATE WORK WILL START: 6/30/2006	23. ESTIMATED DURATION: 2 weeks	

24. PROPOSED CASING AND CEMENTING PROGRAM							
SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT			SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT		
12.25"	8.625"	J-55	24#	300	Class G	210+/- sacks	1.18 ft3/sx 15.7 ppg
7.875"	5.5"	J-55	15.5#	2,520	CBM light wt - lead	230+/- sacks	4.14 ft3/sx 10.5 ppg
					Class G - tail	210+/- sacks	1.62 ft3/sx 14.2 ppg

25. **ATTACHMENTS**

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:

<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN
<input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER	<input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER

NAME (PLEASE PRINT) Kyla Vaughan TITLE Regulatory Compliance Tech

SIGNATURE Kyla Vaughan DATE 4/10/2006

(This space for State use only)

CC: SITA

API NUMBER ASSIGNED: 43-015-36679

Approved by the
Utah Division of
Oil, Gas and Mining


Date: 05-16-06
By: [Signature]

RECEIVED
APR 13 2006

DIV. OF OIL, GAS & MINING

Township 17 South

Range 8 East



Legend

- Drill Hole Location
- ⊙ Brass Cap (Found)
- Brass Cap (Searched for, but not found)
- △ Calculated Corner
- () GLO
- GPS Measured

NOTE:

UTM AND LATITUDE / LONGITUDE COORDINATES ARE DERIVED USING A GPS PATHFINDER AND ARE SHOWN IN NAD 27 DATUM.

LAT / LONG
39°19'43.828" N
111°01'30.398" W

Location:

THE WELL LOCATION WAS DETERMINED USING A TRIMBLE 4700 GPS SURVEY GRADE UNIT.

Basis of Bearing:

THE BASIS OF BEARING IS GPS MEASURED.

GLO Bearing:

THE BEARINGS INDICATED ARE PER THE RECORDED PLAT OBTAINED FROM THE U.S. LAND OFFICE.

Basis of Elevation:

BASIS OF ELEVATION OF 6495' BEING AT THE SOUTHEAST SECTION CORNER OF SECTION 20, TOWNSHIP 17 SOUTH, RANGE 8 EAST, SALT LAKE BASE & MERIDIAN, AS SHOWN ON THE RED POINT QUADRANGLE 7.5 MINUTE SERIES MAP.

Description of Location:

PROPOSED DRILL HOLE LOCATED IN THE NW 1/4 SE 1/4 OF SECTION 21; BEING 2862.23' SOUTH FROM THE NORTH LINE AND 3717.08' EAST FROM THE WEST LINE OF SECTION 21, T17S, R8E, SALT LAKE BASE AND MERIDIAN.

Surveyor's Certificate:

I, ALBERT J. SPENSKO, A REGISTERED PROFESSIONAL LAND SURVEYOR, HOLDING CERTIFICATE 146652 STATE OF UTAH, DO HEREBY CERTIFY THAT THE INFORMATION ON THIS DRAWING IS A TRUE AND ACCURATE SURVEY BASED ON DATA OF RECORD AND WAS CONDUCTED UNDER MY PERSONAL DIRECTION AND SUPERVISION AS SHOWN HEREON.



GRAPHIC SCALE

0 500' 1000'
(IN FEET)
1 inch = 1000 ft.



TALON RESOURCES, INC.

195 N. 100 W., P.O. Box 1230
Huntington, Utah 84528
Phone (435)687-5310 Fax (435)687-5311
E-Mail talon@etv.net



State of Utah #17-8-21-33
Section 21, T17S, R8E, S.L.B.&M.
Emery County, Utah

Drawn By: J. STANSFIELD	Checked By: L.W.J.
Drawing No. A-1	Date: 02/22/06
	Scale: 1" = 1000'
Sheet 1 of 4	Job No. 2057

From: Ed Bonner
To: Whitney, Diana
Date: 5/8/2006 3:48:33 PM
Subject: Well Clearance

The following wells have been given cultural resource clearance by the Trust Lands Cultural Resources Group:

ConocoPhillips Company

Utah 17-1174
Utah 17-1175
Utah 13-1169
Utah 19-1181
Utah 20-1183
Utah 24-1189
Utah 30-1062
Utah 30-1088
Utah 30-1090

Lone Mountain Production Company
Hancock State 2-5

Pendragon Energy Partners, Inc
State 9-16-10-18

QEP Uinta Basin, Inc
GB 9ML-16-8-22
GB 10ML-16-8-22
RW 12-32BG

Westport Oil & Gas Company

NBU 921-34J
NBU 922-31N
NBU 1021-4B
NBU 1021-4G
NBU 1021-4H
NBU 922-31O
NBU 921-32N (1 significant site which must be avoided per arc consultant survey in relocating well pad)
NBU 921-32O

XTO Energy, Inc

State of Utah 17-8-28-12
State of Utah 17-8-21-33
State of Utah 17-8-22-14
State of Utah 17-8-18-24
State of Utah 17-8-5-42R

If you have any questions regarding this matter please give me a call.

CC: Davis, Jim; Garrison, LaVonne; Hill, Brad; Hunt, Gil

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER _____

2. NAME OF OPERATOR:
XTO ENERGY INC.

3. ADDRESS OF OPERATOR:
2700 Farmington Ave. Bldg K CITY Farmington STATE NM ZIP 87401

PHONE NUMBER:
(505) 324-1090

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 2433' FSL & 1517' FEL

COUNTY: EMERY

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWSE 21 17S 08E

STATE: UTAH

5. LEASE DESIGNATION AND SERIAL NUMBER:
ML-48176

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:
STATE OF UTAH #17-08-21-33

9. API NUMBER:
4301530679

10. FIELD AND POOL, OR WILDCAT:
FERRON SANDSTONE

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: MONTHLY REPORT
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Attached is an activity period for this well from May 1 - June 21, 2006.

NAME (PLEASE PRINT) HOLLY C. PERKINS

SIGNATURE

Holly C. Perkins

TITLE REGULATORY COMPLIANCE TECH

DATE 6/21/2006

(This space for State use only)

RECEIVED
JUN 20 2006

DIV. OF OIL, GAS & MINING

Farmington Well Workover Report

STATE OF UTAH	Well # 17-08-21-33	
---------------	--------------------	--

Objective: Drill & Complete

**First
Report:** 06/13/2006

AFE: 650456

6/13/06 Notified Carol Daniels, (State of Utah, Price, Utah) & Dan Jarvis, (DOGM, SLC) on 5/24/06 regarding pending construction. Built new loc, acc road & res pit. Lnd res pit. Notified Carol Daniels, (State of Utah, Price, Utah) & Dan Jarvis, (DOGM, SLC) on 5/24/06 regarding conductor csg. Susp rpts pending further activity.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: XTO ENERGY INC. Operator Account Number: N 2615
Address: 2700 FARMINGTON AVE K #1
city FARMINGTON
state NM zip 87401 Phone Number: (505) 324-1090

Well 1

43-015-30679

API Number	Well Name		QQ	Sec	Twp	Rng	County
<u>4301530641</u>	STATE OF UTAH 17-8-21-33		NWSE	21	17S	08E	EMERY
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
<u>A</u>	<u>99999</u>	<u>15468</u>	<u>6/13/06</u>		<u>6/29/06</u>		
Comments: <u>well spudded 6/13/06</u> <u>FRSD</u>							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
Comments:							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
Comments:							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

HOLLY C. PERKINS

Name (Please Print)

Signature

Regulatory Compliance Tech 6/29/2006

Title

Date

RECEIVED

JUN 29 2006

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-48176
2. NAME OF OPERATOR: XTO ENERGY INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 2700 Farmington Ave. Bldg K Farmington STATE NM ZIP 87401		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2433' FSL & 1517' FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWSE 21 17S 8E S		8. WELL NAME and NUMBER: STATE OF UTAH 17-8-21-33 9. API NUMBER: 4301530679 10. FIELD AND POOL, OR WILDCAT: FERRON SANDSTONE
		COUNTY: EMERY STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/RESUME) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input checked="" type="checkbox"/> OTHER: SPUD

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. notified Mark Jones w/DOGM of spud taking place @ 4:30 pm, 6/15/06. Drilled to 32' GL. Set 32' of 13-3/8" csg @ 32' GL. Cmt'd w/6 cu yds Reddi Mix cmt. Drilled 12-1/4" hole to 315'. Ran 7 jts 8-5/8", 24#, J-55 ST&c csg. Set csg @ 309'. Cmt'd surf csg w/220 sx Class G cmt w/2% CaCl @ 1/4#/sx Flocele (15.6 ppg, 1.15 cuft/sx). Circ 11.5 to surf.

Reached driller's TD on 7/4/06 @ 2740'.

Drilling ahead . . .

NAME (PLEASE PRINT) HOLLY C. PERKINS SIGNATURE	TITLE REGULATORY COMPLIANCE TECH DATE 7/18/2006
--	--

(This space for State use only)

RECEIVED
JUL 26 2006



TABULATION OF DEVIATION TESTS

XTO Energy Inc.

Depth	Degrees	Depth	Degrees	Depth	Degrees
293'	1/4 °	1098'	2 1/2 °	1916'	2 3/4 °
313'	1/4 °	1199'	2 1/4 °	2017'	2 3/4 °
412'	1 3/4 °	1299'	2 3/4 °	2118'	2 °
474'	1 1/4 °	1400'	3 °	2218'	2 3/4 °
577'	1 1/2 °	1474'	2 3/4 °	2318'	2 1/8 °
677'	2 °	1535'	2 3/4 °	2439'	3 °
777'	2 °	1635'	2 1/2 °	2539'	2 1/2 °
897'	2 °	1735'	2 1/4 °	2639'	2 °
1008'	2 3/4 °	1836'	2 1/4 °	2740'	2 1/4 °

A F F I D A V I T

THIS IS TO CERTIFY that to the best of my knowledge the above survey details the deviation tests taken on XTO ENERGY INC'S

State of Utah 17-8-21-33
in Section 21, T17S, R8E,
API # 43-015-30679
Emery County, Utah.

Signed

Brent H. Martin

Printed Name

Brent H. Martin

Title

Drilling Manager


THE STATE OF NEW MEXICO)

) SS.

COUNTY OF SAN JUAN)

BEFORE ME, the undersigned authority, on this day personally, Brent H. Martin, known to me to be Drilling Manager for XTO Energy Inc and to be the person whose name is subscribed to the above statement, who, being by me duly sworn on oath, states that he has knowledge of the facts stated herein and that said statement is true and correct.

SUBSCRIBED AND SWORN to before me, a Notary Public in and for said County and State the 21st day of July, 2006.



Holly C. Perkins

My Commission Expires:

9-1-2008

RECEIVED
JUL 26 2006

NOTARY PUBLIC & MINIST

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐ FORM 8
(highlight changes)

5. LEASE DESIGNATION AND SERIAL NUMBER:
ML-48176

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT or CA AGREEMENT NAME

8. WELL NAME and NUMBER:
STATE OF UTAH 17-8-21- 33

9. API NUMBER:
4301530679

10 FIELD AND POOL, OR WILDCAT
FERRON SANDSTONE

11. QTR/QTR, SECTION, TOWNSHIP, RANGE,
MERIDIAN:
NWSE 21 17S 8E

12. COUNTY
EMERY

13. STATE
UTAH

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL ☐ GAS WELL ☒ DRY ☐ OTHER

b. TYPE OF WORK: NEW WELL ☒ HORIZ. LATS. ☐ DEEP-EN ☐ RE-ENTRY ☐ DIFF. RESVR. ☐ OTHER

2. NAME OF OPERATOR:
XTO Energy Inc.

3. ADDRESS OF OPERATOR:
2700 Farmington Ave K1 CITY Farmington STATE NM ZIP 87401

PHONE NUMBER:
(505) 324-1090

4. LOCATION OF WELL (FOOTAGES)
AT SURFACE: 2433' FSL & 1517' FEL

AT TOP PRODUCING INTERVAL REPORTED BELOW:

AT TOTAL DEPTH:

14. DATE SPUDDED: 6/15/2006

15. DATE T.D. REACHED: 7/3/2006

16. DATE COMPLETED: 9/30/2006

ABANDONED ☐ READY TO PRODUCE ☒

17. ELEVATIONS (DF, RKB, RT, GL):
6239'

18. TOTAL DEPTH: MD 2,740
TVD

19. PLUG BACK T.D.: MD 2,696
TVD

20. IF MULTIPLE COMPLETIONS, HOW MANY? *

21. DEPTH BRIDGE MD
PLUG SET: TVD

22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each)

GR/CBL/CCL

23.

WAS WELL CORED? NO ☐ YES ☐ (Submit analysis)

WAS DST RUN? NO ☐ YES ☐ (Submit report)

DIRECTIONAL SURVEY? NO ☐ YES ☐ (Submit copy)

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
17"	13 3/4 J55			32		RM 6		0	0
12 1/4"	8 5/8 J55	24#		308		G 220		0	0
7 7/8"	5 1/2 J55	15.5#		2,740		III 130		0	0

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2 7/8	2,599							

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
(A) FERRON COAL	2,255	2,406			2,395 2,406	0.41	33	Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(B)					2,255 2,270	0.41	45	Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(C)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
(D)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
2255' - 2406'	Acidized w/1977 gals 15% HCl acid. Frac'd w/12,272 gals 20# linear gel, 134,981 gal 20# Delta 140 frac fld carrying 172,800# 20/40 and 121,200# 16/30 Brady sand.

29. ENCLOSED ATTACHMENTS:

☐ ELECTRICAL/MECHANICAL LOGS ☐ GEOLOGIC REPORT ☐ DST REPORT ☐ DIRECTIONAL SURVEY

☐ SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION ☐ CORE ANALYSIS ☐ OTHER:

30. WELL STATUS:

31. INITIAL PRODUCTION

INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED: 9/30/2006	TEST DATE: 10/2/2006	HOURS TESTED: 24	TEST PRODUCTION RATES: →	OIL – BBL: 0	GAS – MCF: 18	WATER – BBL: 228	PROD. METHOD: P
CHOKE SIZE: N/A	TBG. PRESS. 85	CSG. PRESS. 490	API GRAVITY 0.63	BTU – GAS 990	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

TO BE SOLD

33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof. Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
				MANCOS MARKER	2.099
				UPPER FERRON SS	2.220
				LOWER FERRON SS	2.408
				TUNUNK SHALE	2.658

35. ADDITIONAL REMARKS (Include plugging procedure)


36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT)

HOLLY C. PERKINS

TITLE REGULATORY COMPLIANCE TECH

SIGNATURE



DATE 10/3/2006

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation

- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

** ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

EMERY

STATE OF UTAH 17-8-21-33

LOCATION: Sec 21, T17S, R8E
 CONTRACTOR: Leon Ross Drilling, 27
 WI %:
 AFE#: 650456
 API#: 43015306790000
 DATE FIRST RPT: 6/18/2006

RECEIVED

OCT 02 2006

DIV. OF OIL, GAS & MINING

DATE: 6/18/2006
 OPERATION: WOC
 DFS: 2.56 Footage Made: 32 Measured Depth: 32
 MW: VISC:
 WOB: 22 RPM: 8
 DMC: CMC: DWC: 4,197.00 CWC: 4,197.00
 TIME DIST: (24.00) MIRU Leon Ross Rig #27. Spud Notification to Mark Jones w/DOGM Spud @ 4:30pm, 6-15-06. Drill to 60w/ air foam. Set 32' of 13 3/8 @ 32' of 13 3/8" @32' GL. Cmt w/ 6 cu yds Reddi Mix cmt outside & fill hole. PU 12 1/4" air tools. WOC. SDFN..

DATE: 6/19/2006
 OPERATION: WORT
 DFS: 3.56 Footage Made: 276 Measured Depth: 308
 MW: VISC:
 WOB: RPM:
 DMC: CMC: DWC: 19,220.00 CWC: 23,417.00
 TIME DIST: (24.00) Drill 12 1/4" hole to 31 5'. Blow Cin. RU & run surf csg as follows. 8 5/8" bull nose G S, 8 5/8" shoe jt w/ insert fit, 7 jts 8 5/8 #24, J55, ST&C csg. Csg set @ 308.23 GL. Fit @ 268.51' GL. Cent csg w. 4 bow spring cents. MIRU Halliburton. Cmt surf csg w/ 220 sx Class G cmt w/ 2% CaCl @ 1/4#/sx. Flocele (density 15.6 ppg. yld 1.15). Displaced w/ 16 bfw. LD Plug 12' above first float. Circ 11.5 to surf. Did not fall. Float held. SWI. RDMO Halliburton. RDMO Leon Ross Drig #27. Susp report pending further activity..

DATE: 6/23/2006
 OPERATION: Run WL Surv on surf
 DFS: 7.56 Footage Made: 0 Measured Depth: 308
 MW: VISC:
 WOB: RPM:
 DMC: CMC: DWC: CWC: 23,417.00
 TIME DIST: (24.00) RU WL. Run WLS: 1deg @ 230'. RD WL..

DATE: 7/1/2006
 OPERATION: Drig @ 333'
 DFS: 15.56 Footage Made: 25 Measured Depth: 333
 MW: VISC:
 WOB: 2 RPM: 60
 DMC: CMC: DWC: 17,600.15 CWC: 41,017.15
 TIME DIST: (5.75) Move and Rig Up. (0.25) Safety Meeting. (3.50) Nipple Up BOP. (3.00) Pressure Test Blind and Pipe Rams, Choke manifold Valves, Choke Line, to 250# low F/ 5 min and 2000# High F/ 10 Min. Pressure Test Surface Csg to #1000 for 30 min.. (1.00) Rig Up Blooie Line. (2.00) Finish Rig Up. Level Rig. (2.25) Pick up Hammer and Bit. (0.50) Safety Meeting. (0.25) Test Fire Hammer. (3.00) Pick Up BHA and Trip in Hole Tag Cement @233'. (2.00) Drig Cement. (0.25) Wireline Survey @293' was .25 degree. (0.25) Drig.

DATE: 7/2/2006
 OPERATION: Drig @ 1299'
 DFS: 16.56 Footage Made: 966 Measured Depth: 1,299
 MW: VISC:
 WOB: 2 RPM: 60
 DMC: CMC: DWC: 30,388.85 CWC: 71,406.00
 TIME DIST: (0.25) WLS @313'. (0.25) Function test Pipe Rams. (1.50) Drig 333 to 415. (0.50) WLS @ 415. (1.00) Drig 415' to 476'. (0.50) WLS @476'. (1.75) Drig 476' to 536'. (0.25) Safety Meeting. (1.00) Drig 536' to 577'. (0.50) WLS @ 577' was 1.5. (0.50) Drig 577' to 677'. (0.50) WLS @ 677' was 2. (1.00) Drig 677' to 777'. (0.50) WLS @ 777 was 2. (1.00) Drig 777' to 817'. (0.25) WLS @ 897 was 2. (1.75) Drig 817 to 918'. (0.50) WLS @ 977' was 2.75. (3.00) Drig 918' to 1008'. (0.25) WLS @ 977' was 2.75. (1.75) Drig 1008' to 1098'. (0.50) WLS @ 1077' was 2.5. (1.00) Drig 1098' to 1199'. (0.50) WLS @ 1199' was 2.25. (2.50) Drig 1199' to 1299'. (1.00) WLS @ 1299' was 2.75.

DATE: 7/3/2006

OPERATION: Drlg @ 2178'
DFS: 17.56 **Footage Made:** 879 **Measured Depth:** 2,178
MW: **VISC:**
WOB: 1 **RPM:** 60
DMC: **CMC:** **DWC:** 52,815.75 **CWC:** 124,221.75
TIME DIST: (4.00) Drlg 1299' to 1400'. (0.50) WLS @ 1400' was 3. (1.25) POOH, Lay Down IBS and NBS. (0.50) Safety Meeting. (2.75) Trip In Hole. (0.50) Drlg 1400' to 1474'. (0.50) WLS @ 1474' was 2.75. (0.50) Drlg 1474' to 1535'. (0.50) WLS @ 1535' was 2.75. (2.00) Drlg 1535' to 1635'. (0.50) WLS @ 1635' was 2.25. (1.00) Drlg 1635' to 1735'. (0.50) WLS @ 1735' was 2.25. (2.00) Drlg 1735' to 1836'. (0.50) WLS @ 1836' was 2.25. (1.50) Drlg 1836' to 1936'. (0.50) WLS @ 1936' was 2.75. (1.00) Drlg 1936' to 2038'. (0.50) WLS @ 2038' was 2.75. (2.00) Drlg 2038' to 2138'. (0.50) WLS @ 2138' was 2.0. (0.50) Drlg 2138' to 2178'.

DATE: 7/4/2006
OPERATION: Logging Well @ 2740'
DFS: 18.56 **Footage Made:** 562 **Measured Depth:** 2,740
MW: **VISC:**
WOB: 2 **RPM:** 60
DMC: **CMC:** **DWC:** 60,578.25 **CWC:** 184,800.00
TIME DIST: (0.25) Function Test Pipe Rams. (0.75) Drlg 2178' to 2238'. (0.50) WLS @ 2278' was 2.75. (2.50) Drlg 2238' to 2338'. (0.50) WLS @ 2338' was 2.25. (1.25) Drlg 2338' to 2378'. (0.25) Safety Meeting. (0.50) Drlg 2378' to 2439'. (0.50) WLS @ 2439' was 2.50. (2.50) Drlg 2439' to 2539'. (0.50) WLS @ 2539' was 2.5. (2.50) Drlg 2539' to 2639'. (0.50) WLS @ 2639' was 2.0. (2.00) Drlg 2639' to 2740' T.D.. (0.50) WLS @ 2740' was 2.25. (1.00) Blow Hole. (1.25) POOH Laying Down D.P.. (0.25) Safety Meeting. (2.00) Lay Down DP and BHA. (1.50) Wait On Loggers. (2.50) Rig Up Schlumberger and Log.

DATE: 7/5/2006
OPERATION: Waiting on Location
DFS: 19.56 **Footage Made:** 0 **Measured Depth:** 2,740
MW: **VISC:**
WOB: **RPM:**
DMC: **CMC:** **DWC:** 50,195.05 **CWC:** 234,995.05
TIME DIST: (3.50) Logging W/ Schlumberger. (2.25) Rig up and Run 5 1/2" Csg. (0.25) Safety Meeting. (1.50) Run Casing. (0.50) Rig Up Haliburton and Hold Safety Meeting. (2.00) Cement. (4.00) Nipple Down BOP, Set Slips, Cut Off Casing. (4.00) Finish Nipping Down,. (6.00) Rig Down, Wait on Location, Released Rig at 2400 hr..

Farmington Well Workover Report

STATE OF UTAH	Well # 17-08-21-33	FERRON SANDSTON
----------------------	---------------------------	------------------------

Objective: Drill & Complete

First Report: 06/13/2006

AFE: 650456

6/13/06 Cont rpt for AFE #650456 to D&C Ferron Coal well fr/ 7-4-06 to 7-25-06. NU frac vlv. MIRU Express Hot Oil. PT csg, WH & frac valve to 4,000 psig for 30". Tstd OK. RDMO Express. MIRU Bran-Dex WL. Run GR/CCL/CBL fr/ 2,697' to surf. Log showed gd cmt bond fr/1,330' - 1,900', bad cmt bond fr/1,900' - 2,220', gd bond fr/2,220' - 2,535', bad cmt fr/2,535' - 2,697'. TOC @ 1,330' FS. RDMO WL. Susp rpts to further activity.

7/6/06 Wellview has all the drilling details and accumulated cost.

8/2/06 Cont rpt for AFE #650456 to D&C Ferron Coal well. Build sep & mtr run pad. Set new CIP Inc 30" x 10', 500 psig WP, 2 ph, vert sep w/heated wtr bath (SN 4209), 250 MBTU burner & new Daniel 3" 150 C mtr run w/Daniel flgs (SN 05220112) fr/XTO stk. Dug trench fr/WH to sep & mtr run. Inst & conn welded 4" S40 FB pipe FL fr/WH tbg mnfd to sep inl. Inst & conn 6" welded S 40 FB pipe FL fr/WH csg mnfd to sep inl. Dug trench fr/sep to sales ln. Inst & conn welded 6" S40 FB pipe gas sales ln fr/mtr run to sales ln. Inst & conn 4" S 40 FB pipe fr/sep dmp to wtr ln. Inst & conn new 3 hp Baldor elec motor (SN# FO605013276) fr/Industrial Electric on new Ebara 1" inl x 1" otl, 170 BWPd, centrifugal wtr trans pmp (SN# BG4210286) on sep wtr dump ln. Backfill trench. Clnd loc. Susp rpts pending further activity.

8/22/06 Cont rpt for AFE # 650456 to D & C Ferron Coal well fr/ 7-25-06 to 8-22-06. MIRU Bran-DEX WL. RIH w/4" Slick Csg Guns. Perf L/Ferron Coal w/3 JSPF & 120 deg ph @ 2,395' - 2,406', (Titan EXP-3323-322T chrgs, 22.7 gm, .41" dia, 33 holes). All dpts correlated fr/Brad-Dex CBL-GR-CCL log ran on 7-24-06. POH & LD csg gun. RDMO Bran-Dex WLU. SWI. SDFN.

8/23/06 SICP 0 psig. MIRU Bran-Dex WL. RIH w/dump blr & dmpd 10 gals 28 % HCL @ 2,402'. POH & LD dump blr. MIRU Halliburton frac crew. Ac L/Ferron Coal perfs fr/2,395' - 2,406' dwn 5-1/2" csg w/977 gals 15% HCL at 30 BPM & 1,800 psig. Form BD @ 30 bpm & 2,866 psig. Frac L/Ferron Coal perfs fr/2,395' - 2,406' w/7,189 gals 20# Linear Gel. 88,492 gals 20# Delta 140 frac fld carrying 82,200 lbs 20/40 Brady sd, & 101,200 lbs 16/30 Brady sd. Frac Gradient 0.82. Flshd w/2,357 gals 20# Linear Gel, 3 bbls short. Sd Conc 0.25 - 5.10 ppg. All sd coated w/sd wedge NT. ISIP 1,199 psig, 5" SIP 1,022 psig, 10" SIP 922 psig, 15" SIP 854 psig. ATP 1,888 psig. AIR 26 bpm. Max TP 2,866 psig. Max IR 30.90 bpm. Max sd conc 5.10 ppg. 2,278 BLWTR (L/Ferron). RD Halliburton. RU Bran-DEX WL. RIH & set 5-1/2" CBP @ 2,350'. POH w/ WL. Press tst CBP to 2,000 psig for 5". Tstd OK. RIH w/4" slick Csg Gun. Perf U/Ferron Coal w/3 JSPF 120 deg ph @ 2,255' - 2,270' (45 holes, Titan EXP-3323-322T chrgs 22.7 gm, .41" dia.). All dpts correlated w/Bran-Dex CBL/CCL/GR log Dated 7-24-06. POH. LD csg gun. RDMO Bran-Dex WLU. RU Halliburton frac crew. Ac U/Ferron Coal perfs fr/2,255' - 2,270' dwn 5-1/2" csg w/1,000 gals 15% HCL ac. Form BD @ 5 BPM & 2,100 psig. Frac U/Ferron Coal perfs fr/ 2,255' - 2,270' w/5,083 gals 20# Linear Gel, 45,489 gals 20# Delta 140 frac fld carrying 90,600 lbs 20/40 Brady sd & 20,000 lbs 16/30 Brady sd. Frac Gradient 0.86. Flshd w/2,115 gals 20# Linear Gel, 3 bbls short. Sd Conc 1.00 - 5.00 ppg. All sd coated w/Sd Wedge NT. ISIP 1,152 psig, 5"SIP 936 psig, 10"SIP 747 psig, 15"SIP 610 psig. AIR 30.1 bpm, ATP 1,300 psig. Max TP 2,095 psig. Max IR 31.60 bpm, Max sd conc 5.00 ppg. 3,361 BLWTR (ttl). RDMO Halliburton. SWI. Susp rpts to further activity.

8/24/06 Std fusing 500' for inst of 6" SDR/11 poly gas line 4" SDR/7 poly wtr line. SDFN.

8/31/06 Cont rpt for AFE #650456 to D&C Ferron Coal well. MIRU Nielsons Crane. Built gravel pad. Set new Jesen 8' x 24' x 16" cmt pad, New Lufkin C160D-200-74" PU w/30" gearbox sheave (SN G146101A), Teco 20 hp elec motor (SN Z0603130517) w/8" motor sheave & 3 - C 180 belts fr/XTO stk. RDMO Nielsons Crane. Clnd loc. Susp rpts pending further activity.

9/7/06 Cont rpt for AFE #650456 to D&C Ferron Coal well. Backfill res pit. Susp rpts pending further activity. Compl tie in fr/new 6" SDR/11 poly gas line to new 12" SDR/11 poly gas line & fr/ new 6" SDR/7 poly wtr line to

new 4" SDR/7 poly wtr line. SDFN.

- 9/8/06** Cont rpt for AFE #650456 to D & C Ferron Coal/sd. fr/ 8-23-06-06 to 9-8-06. SICP 0 psig. MIRU BHWS rig# 1. ND frac vlv. NU BOP. PU & TIH w/4-3/4" blade bit, xo, SN & 106 jts 2-7/8", 6.5#, J-55, EUE, 8rd tbg. Tgd fill @ 2,240'. U/Ferron Coal fr/2,255' - 2,270'. CBP @ 2,350'. RU pwr swivel. Estb circ w/50 BFW. CO fill & DO CBP fr/2,240' - 2,350' w/ jts tbg. RD pwr swivel. TIH w/9 jts tbg. Tgd fill @ 2,646'. L/Ferron Coal perfs @ 2,395' - 2,406'. PBTD @ 2,697'. RU pwr swivel. Estb circ w/50 BFW wtr. CO fill fr/2,647' - 2,697' (PBTD) w/2 jts tbg. Circ well cln. RD pwr swivel. TOH w/20 jts tbg. SWI. SDFN. Lost 500 BFW while circ for day. 3,861 BLWTR.
- 9/9/06** SITP 0 psig SICP 0 psig. TIH w/8 jts tbg. EOT @ 2,454. Ferron perfs @ 2,255' - 2,406'. RU swb tls. BFL @ 500' FS. S. 0 BO, 240 BLW, 28 runs, 6 hrs, FFL @ 1,200' FS. Fld smpls on runs 1-7 showed dirty wtr w/tr sd, runs 8-28 showed cln wtr w/no sd. RD swb tls. SICP 0 psig. TIH w/12 jts 2-7/8" tbg. Tgd 3' of fill @ 2,694'. TOH w/12 jts 2-7/8" tbg. EOT @ 2,454'. SWI. SDFWE. 3,621' BLWTR.
- 9/12/06** SITP 0 psig, SICP 0 psig. TOH w/75 jts 2-7/8" tbg. LD BHA. TIH w/2-7/8" x 20' OPMA, 2 jts 2-7/8" tbg, 2707 Cavins Desander, 2-7/8" x 4' tbg sub, 2-7/8" SN & 76 jts 2-7/8", 6.5#, J-55, EUE, 8rd tbg. Ld tbg w/donut tbg hanger. SN @ 2,489'. EOT @ 2,599'. PBTD @ 2,697'. Ferron Coal perfs fr/2,255' - 2,406'. ND BOP. NU WH. Ppd 5 BFW & flshd tbg. PU & loaded 2-1/2" x 2" x 16' RHBC-DV pmp (XTO #103) w/1' X 1" stnr nip. TIH w/pmp, 1 - 7/8" stabilizer rod, 2 - 1-1/2" x 25' sbs, 1 - 7/8" x 4' stabilizer rod, 2 - 1-1/2" x 25' sbs, 1 - 7/8" x 4' stabilizer rod, 2 - 1-1/2" x 25' sbs, 1 - 7/8" x 4' stabilizer rod, 91 - 3/4" gr D skr d w/4 molded guides pr rod, 1 - 3/4" x 6' rod sub & 1-1/4" x 26' PR w/1-1/2" x 14' PR lnr. Seated pmp. PT tbg to 500 psig w/6 BFW for 10". Tstd ok. Rlsd press. LS pmp w/rig to 500 psig. Gd PA. HWO. RDMO BHWS rig #1. Surf equip not ready to start PU. Inst Autopilot RTU #A06FJ209, wtr mtr, power, radio, tbg & csg xmtrs. Inst Allen Bradley elec pmp panel & elec mtr on 320 pmp unit. Ditched in & conn #2 elec cable fr/power ln to panel. Inst elec sep dmp pmp. Auto inst compl. 3,632 BLWTR.

Tubing	Location: Lower		Top Perf: 2,255	Btm Perf: 2,406	OH:	No
	ZONE 1	Desc: Ferron				
				Top	Btm	
	Qty	Type Description	Cond	Depth	Depth	Length
	76	Tubing 2-7/8", 6.5#, J-55, EUE, 8rd Tubing	New	6	2,488	2,481.59'
	1	Tubing 2-7/8" SN	New	2,488	2,489	1.10'
	1	Tubing 2-7/8", 6.5#, J-55, EUE, 8rd Tubing Sub	New	2,489	2,493	4.09'
	1	Tubing 2-7/8" Cavins 2707 Desander	New	2,493	2,513	20.20'
	2	Tubing 2-7/8", 6.5#, J-55, EUE, 8rd Tubing	New	2,513	2,579	65.87'
	1	Tubing 2-7/8" OPMA	New	2,579	2,599	20.00'
					Total	2,592.85'
					Landed @	2,592.85'

- 9/20/06** Cont rpt for AFE #650456 to D&C Ferron Coal well. SITP 0 psig, SICP 0 psig. Std PU @ 6:00 p.m., 9/19/06. Ppg @ 8 x 74" SPM. WO csg to build psig to first deliver gas sales.
- 9/21/06** P. 0 , 85 , 0 MCF, FTP 85 psig, SICP 0 psig, , LP 4 psig, SP 0 psig, DP 0 psig, 6 hrs.
- 9/22/06** P. 0 , 329 , 0 MCF, FTP 140 psig, SICP 0 psig, , LP 18 psig, SP 0 psig, DP 0 psig, 24 hrs.
- 9/23/06** P. 0 , 320 , 0 MCF, FTP 140 psig, SICP 0 psig, , LP 18 psig, SP 0 psig, DP 0 psig, 24 hrs.
- 9/24/06** P. 0 , 300 , 0 MCF, FTP 140 psig, SICP 0 psig, , LP 18 psig, SP 0 psig, DP 0 psig, 24 hrs. FR for AFE #650456 to D & C.

Farmington Morning Report

Thursday, October 26, 2006

Date	Description	Sales Volume	Comment
10/24/06	El Paso	86,053 MCF	LP 135 psig
10/24/06	Western Gas	3,067 MCF	LP 282 psig
10/24/06	Williams	29,750 MCF	LP 119 psig
10/24/06	Durango	62,721 MCF	LP 311 psig
10/24/06	Raton	45,457 MCF	LP 1,192 psig
10/24/06	Utah	19,711 MCF	LP 499 psig
10/24/06	Fuel Estimated	17,222 MCF	
10/24/06	TOTAL	263,981MCF	

STATE OF UTAH	Well # 17-08- 21-33	FERRON SANDSTON	Emery, UT
---------------	------------------------	--------------------	-----------

Objective: Drill & Complete

FrcstGas: 0 MCFPD

Prev Gas: 0 MCFPD

AFE: 650456

1st Rept: 06/13/2006

10/1/06 P. FTP 85 psig, SICP 500 psig. OWU @ 11:30 a.m., 9/30/06. Delivered first gas sales to Questar via XTO's HT CDP. IFR 36 MCFPD. Ppg @ 8 x 74" SPM.

DWC: \$0

CWC: \$655,963

DMC: \$0

CMC: \$0

FrcstGas: 0 MCFPD

Prev Gas: 0 MCFPD

10/2/06 P. 0 BO, 228 BW, 18 MCF, FTP 85 psig, FCP 490 psig, LP 8 psig, 24 hrs.

DWC: \$0

CWC: \$655,963

DMC: \$0

CMC: \$0

FrcstGas: 0 MCFPD

Prev Gas: 0 MCFPD

10/3/06 P. 0 BO, 257 BW, 38 MCF, FTP 80 psig, FCP 480 psig, LP 8 psig, 24 hrs.

DWC: \$0

CWC: \$655,963

DMC: \$0

CMC: \$0

FrcstGas: 0 MCFPD

Prev Gas: 0 MCFPD

10/4/06 P. 0 BO, 293 BW, 40 MCF, FTP 80 psig, FCP 475 psig, LP 8 psig, 24 hrs. FR for Compl.

DWC: \$0

CWC: \$655,963

DMC: \$0

CMC: \$0

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

4301530679

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER _____

2. NAME OF OPERATOR:
XTO ENERGY INC.

3. ADDRESS OF OPERATOR:
2700 Farmington, Bldg K-1 CITY Farmington STATE NM ZIP 87401

PHONE NUMBER:
(505) 324-1090

5. LEASE DESIGNATION AND SERIAL NUMBER:
UTU-73965

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:
LM LEMMON #10-01

9. API NUMBER:
Various (see attached)

10. FIELD AND POOL, OR WILDCAT:
FERRON SANDSTONE

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 660' FSK & 792' FEL

COUNTY: EMERY

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN SESE 10 17S 08E

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start 1/1/2004	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input checked="" type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12 DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. acquired wells from Chevron/Texaco on August 1, 2004. Chevron/Texaco failed to file a Notice of Intent to surface commingle these wells and XTO Energy Inc. was unaware until recently that nothing had been filed. We are including with this application for surface commingle a list of the wells in Emery County and a spreadsheet showing production figures for these wells. Each well has its own meter then runs through a central delivery point where allocations are made.

XTO Energy Inc. is requesting approval for the commingle of these wells as well as off-lease measurement. As wells are drilled, additional sundries will be submitted to add to our surface commingle.

COPY SENT TO OPERATOR
Date: 6-12-07
Initials: DM

NAME (PLEASE PRINT) HOLLY C. PERKINS

TITLE REGULATORY COMPLIANCE TECH

SIGNATURE *Holly C. Perkins*

DATE 5/15/2007

This space for State use only)

APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING
DATE: 6/11/07
BY: *[Signature]*

Federal Approval Of This
Action Is Necessary

RECEIVED
MAY 18 2007

DIV. OF OIL, GAS & MINING

Utah Wells Surface Commingled at Huntington CDP

Well Name	API #	Status	Lease
American West Group 15-128	43-015-30484	Shut In	State
Conover 14-171	43-015-30529	Producing	State
Gardner Trust 16-121	43-015-30478	Producing	State
Lemmon LM 10-01	43-015-30242	Producing	Federal
Malone 14-131	43-015-30556	Producing	State
Rowley 08-111	43-015-30486	Producing	State
Seeley 08-112	43-015-30495	Producing	State
Seeley Farms 09-117	43-015-30501	Producing	State
State of Utah 16-8-31-12D	43-015-30608	Producing	State
State of Utah 16-8-31-32DX	43-015-30634	Producing	State
State of Utah 16-8-31-44D	43-015-30606	Producing	State
State of Utah 16-8-32-43	43-015-30566	Producing	State
State of Utah 17-8-15-14	43-015-30622	Producing	State
State of Utah 17-8-15-33	43-015-30561	Producing	State
State of Utah 17-8-17-32	43-015-30672	Producing	State
State of Utah 17-8-18-12	43-015-30626	Producing	State
State of Utah 17-8-18-24	43-015-30678	Producing	State
State of Utah 17-8-18-31	43-015-30671	Producing	State
State of Utah 17-8-18-43	43-015-30670	Producing	State
State of Utah 17-8-20-22	43-015-30623	Producing	State
State of Utah 17-8-21-33	43-015-30679	Producing	State
State of Utah 17-8-21-41	43-015-30631	Producing	State
State of Utah 17-8-22-14	43-015-30676	Producing	State
State of Utah 17-8-22-21	43-015-30624	Producing	State
State of Utah 17-8-28-12X	43-015-30699	Producing	State
State of Utah 17-8-3-11X	43-015-30635	Producing	State
State of Utah 17-8-4-21	43-015-30620	Producing	State
State of Utah 17-8-5-42R	43-015-30686	Producing	State
State of Utah 17-8-7-34	43-015-30621	Producing	State
State of Utah 17-8-8-14	43-015-30673	Producing	State
State of Utah 36-138	43-015-30550	Producing	State
State of Utah 36-139	43-015-30530	Producing	State
State of Utah AA 07-105	43-015-30497	Producing	State
State of Utah AA 07-106	43-015-30396	Producing	State
State of Utah AA 07-146	43-015-30569	Producing	State
State of Utah BB 04-116	43-015-30503	Producing	State
State of Utah BB 05-107	43-015-30479	Producing	State
State of Utah BB 05-108	43-015-30480	Producing	State
State of Utah BB 05-109	43-015-30481	P&A	State
State of Utah BB 05-110	43-015-30482	Producing	State
State of Utah BB 08-113	43-015-30496	Shut In	State
State of Utah BB 09-119	43-015-30437	Producing	State
State of Utah BB 09-120	43-015-30444	Producing	State
State of Utah CC 03-161	43-015-30552	Producing	State
State of Utah CC 10-123	43-015-30454	Producing	State
State of Utah CC 10-124	43-015-30438	Producing	State
State of Utah FF 10-125	43-015-30458	Producing	State
State of Utah FF 11-129	43-015-30459	Producing	State
State of Utah FF 11-130	43-015-30462	Shut In	State

Utah Wells Surface Commingled at Huntington CDP

State of Utah FO 02-186	43-015-30533	Producing	State
State of Utah FO 02-188	43-015-30553	Producing	State
State of Utah GG 03-122	43-015-30499	Producing	State
State of Utah GG 04-115	43-015-30504	Producing	State
State of Utah HH 03-133	43-015-30500	Producing	State
State of Utah II 36-95	43-015-30509	Producing	State
State of Utah II 36-96	43-01530508	Shut In	State
State of Utah KK 32-144	43-015-30567	Producing	State
State of Utah QQ 31-201	43-015-30592	Producing	State
State of Utah SS 22-165	43-015-30520	Producing	State
State of Utah T 36-10	43-015-30268	Producing	State
State of Utah T 36-100	43-015-30506	Producing	State
UP&L 06-102	43-015-30441	Producing	State
UP&L 06-103	43-015-30483	Producing	State
UP&L 06-104	43-015-30442	Producing	State
UP&L Federal 01-101	43-015-30511	Producing	Federal
Utah Federal 01-205D	43-015-30589	Producing	Federal
* Utah Federal 16-7-35-21	43-015-30602	Producing	Federal
* Utah Federal 16-7-35-32	43-015-30603	Producing	Federal
X Utah Federal 17-7-12-22D	43-015-30605	Producing	Federal
Utah Federal 17-7-12-24D	43-015-30604	Producing	Federal
+ Utah Federal 17-7-12-42	43-015-30591	Producing	Federal
Utah Federal 17-7-12-43	43-015-30601	Producing	Federal
Utah Federal 17-7-3-41D	43-015-30697	Producing	Federal
Utah Federal KK 01-140	43-015-30507	Producing	Federal
Utah Federal KK 01-141	43-015-30559	Producing	Federal
Utah Federal M 06-25	43-015-30292	Producing	Federal
WH Leonard 15-127	43-015-30485	Producing	State
Wm S Ivie 09-118	43-015-30443	Producing	State
Zion's Federal 35-135R	43-015-30521	Producing	Federal
+ Zion's Federal 17-7-2-11	43-015-30590	Producing	Federal
Zion's Federal 35-137	43-015-30587	Producing	Federal

Utah Wells Surface Commingled at Orangeville CDP

Well Name	API #	Status	Lease	Notes
Curtis D&D 14-54	43-015-30319	Shut In	Federal	
Curtis L&M 10-58	43-015-30310	Shut In	Federal	
Curtis L&M 15-67	43-015-30325	Producing	Federal	
Federal A 18-7-26-12	43-015-30445	Producing	Federal	
Federal A 26-02	43-015-30244	Shut In	Federal	
Federal A 26-04	43-015-30246	Shut In	Federal	
Federal A 34-07	43-015-30249	Producing	Federal	
Federal A 35-05	43-015-30248	Producing	Federal	
Federal A 35-06	43-015-30247	Producing	Federal	
Federal A 35-89	43-015-30446	Producing	Federal	
Federal B 21-03	43-015-30243	Shut In	Federal	
Federal C 18-7-23-23R	43-015-30629	Producing	Federal	
Federal C 23-08	43-015-30245	Producing	Federal	
Federal P 03-92	43-015-30448	Producing	Federal	
Federal P 03-93	43-015-30449	Producing	Federal	
Federal T 18-07-22-34	43-015-30452	Producing	Federal	
Federal T 22-69	43-015-30451	Producing	Federal	
Federal T 27-87	43-015-30456	P&A	Federal	
Ferron St 4-36-18-7	43-015-30253	Producing	Federal	Operator: Merrion Oil & Gas
Jensen AL 27-09	43-015-30259	Shut In	State	
Jones D&A 09-59	43-015-30329	Producing	Federal	
Jones D&A 15-68	43-015-30318	Shut In	State	
Klinkhammer 1	43-015-30610	Shut In	Federal	Operator: Merrion Oil & Gas
Norris RG 14-40	43-015-30324	Producing	Federal	
Peacock 07-64	43-015-30327	Producing	Federal	
Peacock P&K 08-62	43-015-30320	Producing	Federal	
Peacock Trust 08-61	43-015-30326	Producing	Federal	
Peacock Trust 08-63	43-015-30328	Producing	Federal	
Peacock Trust 09-60	43-015-30321	Producing	Federal	
State of Utah 01-97	43-015-30498	Producing	State	
State of Utah 17-7-36-33R	43-015-30687	Producing	State	
State of Utah 17-8-19-11D	43-015-30695	P&A	State	
State of Utah 18-7-2-33R	43-015-30674	Producing	State	
State of Utah DD 31-98	43-015-30439	Producing	State	
State of Utah II 36-05	43-015-30509	Producing	State	
State of Utah II 36-06	43-015-30508	P&A	State	
State of Utah U 02-11	43-015-30270	Producing	State	
State of Utah U 02-48	43-015-30306	Producing	State	
State of Utah U 02-49	43-015-30309	P&A	State	
State of Utah U 02-50	43-015-30308	Producing	State	
State of Utah X 16-65	43-015-30312	Shut In	State	
State of Utah X 16-66	43-015-30311	Producing	State	
UP&L 14-53	43-015-30313	Producing	State	
UP&L 14-55	43-015-30314	Producing	Federal	
UP&L 23-51	43-015-30315	Producing	Federal	
UP&L 24-57	43-015-30316	Producing	State	
USA 03-74	43-015-30383	Producing	Federal	

Utah Wells Surface Commingled at Orangeville CDP

USA 03-75	43-015-30384	Producing	Federal	
USA 11-72	43-015-30387	Producing	Federal	
USA 18-7-11-23	43-015-30640	Producing	State	
USA 34-80	43-015-30389	Shut In	Federal	
USA 34-82	43-015-30390	Producing	Federal	
Utah Federal 17-7-35-42	43-015-30641	Drilling	Federal	
Utah Federal 18-7-27-44R	43-015-30628	Producing	Federal	
Utah Federal 18-7-9-11	43-015-30639	Producing	Federal	
Utah Federal D 34-12	43-015-30282	Producing	Federal	
Utah Federal D 35-13	43-015-30285	Producing	Federal	
Utah Federal D 35-14	43-015-30286	Producing	Federal	
Utah Federal D 35-15	43-015-30287	Producing	Federal	
Utah Federal H 06-21	43-015-30294	TA	Federal	
Utah Federal P 10-42	43-015-30276	Producing	Federal	
Utah Federal P 10-43	43-015-30277	Producing	Federal	
Utah Federal P 10-47	43-015-30258	Producing	Federal	
Utah Federal Q 04-44	43-015-30280	Producing	Federal	
Utah Federal R 09-45	43-015-30275	Producing	Federal	
Utah Federal S 08-46	43-015-30274	Producing	Federal	
Utah State 01-76	43-015-30381	Producing	State	
Utah State 36-78	43-015-30382	Producing	State	

Apr-05

Ignition Wells

			FIELD ESTIMATED PRODUCTION										ACTUAL ALLOCATED SALES									
WELL No.	Days On	MONTHLY WATER PRODUCTION	Coastal Statement	PROD %	FIELD EST PROD	In Gas	Lse Use Gas	Vented CO2	Vented Gas	VENTED GAS	ADJ	FIELD ESTIMATED SALES	ALLOCATED SALES	Lsa Use Gas	Vented CO2	Vented Gas	VENTED GAS	ADJ	FIELD PRODUCTION			
	10-01	30	435	1478	0.00488716	1479	45	36	98	1708	179	1299	1246	91	98	1708	1708	179	1425			
	T35-10	30	2667	18292	0.06048442	18298	45	447	1708	1708	2200	16095	15424	492	1708	1708	1708	2200	17624			
	M06-25	30	723	18969	0.05610978	16975	45	414	2280	2280	2739	14236	14308	459	2280	2280	2280	2739	17047			
	H06-21	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0			
	07-106	30	879	5052	0.01673803	5064	45	124	789	789	958	4106	4268	169	789	789	789	958	5226			
	09-119	30	85	725	0.0024005	725	45	18	108	108	171	556	912	53	108	108	108	171	783			
	10-124	30	129	951	0.00314458	951	45	23	38	38	106	845	902	68	38	38	38	106	908			
	06-102	30	823	20112	0.0650244	20119	45	491	2219	2219	2755	17354	16959	536	2219	2219	2219	2755	19714			
	06-104	30	809	12922	0.04272795	12925	45	315	2156	2156	2516	10410	10895	350	2156	2156	2156	2516	13412			
	09-118	30	163	797	0.00263536	797	45	19	100	100	164	633	672	64	100	100	100	164	836			
	09-120	30	214	899	0.00297264	899	45	22	80	80	147	752	758	67	80	80	80	147	905			
	18-7-23-23	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0			
	17-8-15-33	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0			
	10-123	30	26	1348	0.0044573	1348	45	33	89	89	167	1182	1137	78	89	89	89	167	1304			
	10-125	30	286	536	0.00177234	536	45	13	32	32	90	446	452	58	32	32	32	90	542			
	11-129	29	0	396	0.00130942	396	44	10	16	16	59	327	334	53	16	16	16	59	403			
	11-130	30	1847	152	0.00053557	152	45	4	7	7	56	106	137	49	7	7	7	56	193			
	16-121	30	275	757	0.0025031	757	45	18	42	42	105	652	638	63	42	42	42	105	743			
	05-107	29	242	8230	0.02721336	8233	44	201	1397	1397	1641	6591	6940	244	1397	1397	1397	1641	8581			
	05-108	30	611	4934	0.01631479	4936	45	120	830	830	965	3940	4160	165	830	830	830	965	5155			
	05-109	30	113	1252	0.00413987	1252	45	31	133	133	209	1044	1056	76	133	133	133	209	1285			
	05-110	30	3	1462	0.00483426	1463	45	36	194	194	275	1188	1233	81	194	194	194	275	1508			
	05-103	30	946	9133	0.03019922	9136	45	223	1241	1241	1509	7627	7701	268	1241	1241	1241	1509	9210			
	15-126	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0			
	15-127	30	1452	3530	0.01167232	3531	45	58	226	226	357	3174	2977	131	226	226	226	357	3334			
	08-111	29	43	1513	0.00500289	1514	44	37	203	203	283	1230	1276	80	203	203	203	283	1559			
	08-112	30	118	1326	0.00438456	1326	45	32	143	143	220	1106	1118	77	143	143	143	220	1338			
	08-113	30	0	756	0.00249979	756	45	18	108	108	171	585	637	63	108	108	108	171	808			
	07-105	30	909	5760	0.02235285	5762	45	165	1197	1197	1407	5355	5700	210	1197	1197	1197	1407	7107			
	03-122	30	0	456	0.00150781	456	45	11	30	30	85	370	385	56	30	30	30	85	471			
	03-133	30	102	331	0.00109449	331	45	8	18	18	71	260	279	53	18	18	18	71	350			
	09-117	30	37	946	0.00312805	946	45	23	136	136	204	742	798	68	136	136	136	204	1002			
	04-116	30	114	603	0.00199388	603	45	15	63	63	123	480	508	60	63	63	63	123	631			
	04-115	30	258	1186	0.00392163	1186	45	29	130	130	204	982	1000	74	130	130	130	204	1204			
	T36-100	30	3714	34839	0.11519881	34851	45	851	5000	5000	5896	28955	29376	896	5000	5000	5000	5896	35272			
	01-140	30	1506	4065	0.01344135	4068	45	99	462	462	606	3460	3428	144	462	462	462	606	4034			
	01-101	30	1199	24478	0.08093908	24486	45	596	2937	2937	3580	20907	20640	643	2937	2937	2937	3580	24220			
	22-165	30	1690	4630	0.01530956	4632	45	113	162	162	320	4312	3904	158	162	162	162	320	4224			
	35-135R	30	4133	1501	0.00496321	1502	0	37	142	142	179	1323	1266	37	142	142	142	179	1445			
	14-171	30	3033	4645	0.01535918	4647	45	113	163	163	321	4325	3917	158	163	163	163	321	4238			
	35-139	30	734	9013	0.02980243	9016	45	220	1062	1062	1327	7699	7600	265	1062	1062	1062	1327	8927			
	02-186	30	193	575	0.0019013	575	45	14	42	42	101	474	465	59	42	42	42	101	586			
	35-138	30	555	5299	0.0175217	5301	45	129	396	396	570	4730	4468	174	396	396	396	570	5038			
	03-161	30	81	558	0.00184509	558	45	14	48	48	113	811	778	68	48	48	48	113	891			
	02-188	30	176	923	0.003052	923	45	23	45	45	71	1804	1659	93	45	45	45	71	1823			
	14-131	30	793	1967	0.00650409	1968	45	48	71	71	164	1827	1862	99	71	71	71	164	2244			
	01-141	30	59	2208	0.00730096	2209	45	54	283	283	392	25047	25466	811	5540	5540	5540	392	32817			
	32-144	30	3738	31387	0.10378441	31398	45	766	5540	5540	6351	2156	2327	57	538	538	538	605	2932			
	07-145	30	672	2760	0.00912623	2761	0	67	538	538	605	10057	9792	284	1276	1276	1276	1560	11352			
	35-137	30	1356	11613	0.0383995	11617	0	284	1276	1276	322	2338	2242	65	257	257	257	322	2584			
	01-205D	30	4123	2659	0.00879226	2660	0	65	257	257	322	29871	29917	866	4755	4755	4755	5621	35538			
	31-201	30	1581	35480	0.11731634	35492	0	866	4755	4755	5621	29871	29917	866	4755	4755	4755	5621	35538			
			43726	302425	1	302529	1930	5	7383	38990	38990	48303	5	254225	5	255009	9312	38990	38990	48302	303311	
												BTU	1.04	SALES MTR		255006						

the Wells

		FIELD ESTIMATED PRODUCTION												ACTUAL ALLOCATED SALES									
		MONTHLY WATER PRODUCTION	Costal Statement	PROD %	FIELD EST PROD	Irr Gas	Lse Use Gas	Vented Gas	Vented Gas	VENTED GAS	ADJ (1)	FIELD ESTIMATED SALES	ALLOCATED SALES	Lse Use Gas (2)	Vented CO2	Vented Gas	TOTAL VENTED	TOTAL ADJ (1)	FIELD PRODUCTION				
Well	Days On																						
B21-03	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
A26-02	26	88	490	0.00165775	490	39	13	15	15	15	67	423	432	52	15	15	15	15	67				
C23-08	30	3432	9140	0.03092205	9,140	45	236	437	437	437	718	8,422	8,062	281	437	437	437	437	718				
A26-04	15	0	68	0.00023005	68	23	2	2	2	2	26	42	60	24	2	2	2	2	26				
A35-06	30	141	29098	0.09844307	29,098	45	750	1,706	1,706	1,706	2,501	26,597	25,665	795	1,706	1,706	1,706	1,706	2,501				
A35-05	18	700	289	0.00097773	289	27	7	7	7	7	41	248	255	34	7	7	7	7	41				
A34-07	30	2845	5383	0.01821153	5,383	45	39	361	361	361	545	4,838	4,748	184	361	361	361	361	545				
P10-47	30	734	39	0.00047026	139	210	4	6	6	6	220	81	123	214	6	6	6	6	220				
A27-09	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
U02-11	30	50211	15291	0.05173154	15,291	45	394	1,255	1,255	1,255	1,694	13,597	13,487	439	1,255	1,255	1,255	1,255	1,694				
S06-46	29	1	519	0.00175588	519	203	13	230	230	230	468	73	458	216	230	230	230	230	468				
R09-45	30	36	444	0.00150212	444	210	11	102	102	102	323	121	392	221	102	102	102	102	323				
P10-42	29	7609	819	0.0027708	819	44	21	144	144	144	208	610	722	65	144	144	144	144	208				
P10-43	30	3050	605	0.00204581	605	45	16	51	51	51	125	483	534	61	51	51	51	51	125				
Q04-44	16	5442	71	0.0002402	71	12	2	11	11	11	125	54	63	114	11	11	11	11	125				
D34-12	24	2583	147	0.00197862	1,471	36	38	126	126	126	208	479	790	68	349	349	349	349	208				
D35-13	30	142110	293	0.0009126	293	36	8	57	57	57	101	192	258	44	57	57	57	57	101				
D35-14	24	647	293	0.00099126	293	36	8	57	57	57	101	192	258	44	57	57	57	57	101				
D35-15	30	1830	20903	0.07071811	20,903	45	539	1,326	1,326	1,326	1,910	18,993	18,436	584	1,326	1,326	1,326	1,326	1,910				
H06-21	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
U02-48	26	7527	2310	0.00781509	2,310	42	60	148	148	148	250	2,060	2,037	102	148	148	148	148	250				
U02-50	30	706	2703	0.00914457	2,703	45	70	165	165	165	280	2,423	2,384	15	165	165	165	165	280				
U02-49	15	173	347	0.00117395	347	23	9	18	18	18	49	298	305	31	18	18	18	18	49				
10-58	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
X16-66	28	307	290	0.00098112	290	42	7	38	38	38	87	203	256	49	38	38	38	38	87				
X16-65	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
14-53	30	298	827	0.00279787	827	45	21	50	50	50	116	711	729	56	50	50	50	50	116				
14-55	30	9023	85522	0.41965343	124,042	90	3,196	7,739	7,739	7,739	11,025	113,017	109,405	3,266	7,739	7,739	7,739	7,739	11,025				
14-55A	30	0	58520	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
23-51	30	175	259	0.00091007	259	45	7	9	9	9	61	208	237	52	9	9	9	9	61				
24-57	30	254	581	0.00230393	581	45	18	22	22	22	85	596	601	63	22	22	22	22	85				
15-68	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
14-54	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
08-62	29	23	491	0.00166113	491	44	13	179	179	179	235	256	433	55	179	179	179	179	235				
09-60	29	1445	1074	0.00363351	1,074	44	28	294	294	294	365	709	947	71	294	294	294	294	365				
14-40	30	4320	2701	0.0091379	2,701	45	70	154	154	154	269	2,432	2,382	115	154	154	154	154	269				
15-67	26	1202	261	0.0008883	261	29	7	14	14	14	60	201	230	46	14	14	14	14	60				
08-61	30	478	9427	0.03189301	9,427	45	243	528	528	528	816	8,611	8,315	288	528	528	528	528	816				
07-64	30	1092	1557	0.00560589	1,557	45	43	495	495	495	583	1,074	1,461	88	495	495	495	495	583				
08-63	30	264	1654	0.00559974	1,654	45	43	495	495	495	583	789	1,459	88	495	495	495	495	583				
09-59	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
01-76	30	3108	4980	0.01684812	4,980	45	128	326	326	326	499	4,481	4,392	173	326	326	326	326	499				
36-78	30	903	5802	0.01962907	5,802	45	150	380	380	380	576	5,227	5,117	195	380	380	380	380	576				
03-74	27	24620	1325	0.00448268	1,325	41	34	130	130	130	105	1,220	1,169	75	130	130	130	130	105				
03-75	30	5579	4396	0.01487235	4,396	45	113	299	299	299	457	3,939	3,877	158	299	299	299	299	457				
11-72	30	45297	922	0.00311927	922	45	24	177	177	177	246	676	813	69	177	177	177	177	246				
34-80	15	44	113	0.0003823	113	24	3	21	21	21	48	65	100	27	21	21	21	21	48				
34-82	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0				
31-98	30	10	1482	0.00501384	1,482	45	38	133	133	133	216	1,266	1,307	83	133	133	133	133	216				
A35-89	30	9902	34803	0.11774398	34,803	45	897	2,021	2,021	2,021	2,963	31,840	30,696	942	2,021	2,021	2,021	2,021	2,963				
P03-92	30	1184	386	0.00299749	386	45	23	89	89	89	157	729	781	68	89	89	89	89	157				
P03-93	28	9434	546	0.00218552	546	42	17	96	96	96	155	491	570	59	96	96	96	96	155				
T22-69	30	320	1130	0.00382297	1,130	45	29	58	58	58	104	460	482	59	58	58	58	58	104				
T27-87	30	574	546	0.0018472	546	45	14	27	27	27	86	460	482	59	27	27	27	27	86				
01-97	30	0	1194	0.00403949	1,194	0	31	73	73	73	104	1,090	1,053	31	73	73	73	73	104				
36-95	30	61	470	0.00159008	470	0	12	49	49	49	61	409	415	12	49	49	49	49	61				
36-95	30	1503	1260	0.00426278	1,260	0	32	130	130	130	162	1,098	1,111	32	130	130	130	130	162				
MERRON GAS WELLS																							
hammer	29	10537	481	0.0016273	481	0	12	15	15	15	27	454	424	12	15	15	15	15	27				
al	4-36-18-7	30	965	493	0.0016679	493	0	0	28	28	2												

LE WELLS FROM CASH STATEMENT

	20777				SALES DIFFERENCE	3575	JC137 %
	0						
	7604			7604			
	2448		2448				
	0		0				
Id statement + memon	974						
	31833		205582	2448	7604	0	

395211	597033	597137	4379	14975	69724	59724	79077	518080	514853	19355	59724	59724	79079	593932
--------	--------	--------	------	-------	-------	-------	-------	--------	--------	-------	-------	-------	-------	--------

OCT 12 2004

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER _____

2. NAME OF OPERATOR:
XTO ENERGY INC. *N2615*

3. ADDRESS OF OPERATOR:
2700 Farmington Bldg K, Sui. Farmington STATE NM ZIP 87401

PHONE NUMBER:
(505) 324-1090

4. LOCATION OF WELL

FOOTAGES AT SURFACE:

COUNTY: Emery

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

STATE: UTAH

5. LEASE DESIGNATION AND SERIAL NUMBER:
Various Leases

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:
See attached list

9. API NUMBER:
Multiple

10. FIELD AND POOL, OR WILDCAT:
Buzzard Bench

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Effective August 1, 2004, the operator changed from Chevron U.S.A. Inc. to XTO ENERGY INC.
for all wells on the attached list.

BLM #579173

State and Fee Bond #104312762

RECEIVED
MAY 18 2007
DIV. OF OIL, GAS & MINING

Kenneth W. Jackson

Kenneth W. Jackson Regulatory Specialist ChevronTexaco for Chevron U.S.A. Inc. *N0210*

NAME (PLEASE PRINT) *James L. Death* TITLE *Vice President-Land*
SIGNATURE *James L. Death* DATE *8/16/04*

(This space for State use only)

APPROVED *9/30/2004*

Earlene Russell
Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

(See Instructions on Reverse Side)

(5/2000)

RECEIVED
SEP 28 2004

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER <u>CONFIDENTIAL</u>		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-67532
2. NAME OF OPERATOR: XTO ENERGY INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 2700 Farmington Ave. Bldg K CITY Farmington STATE NM ZIP 87401		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1815' FNL & 897' FWL		8. WELL NAME and NUMBER: FEDERAL A 18-7-26 #12
5. PHONE NUMBER: (505) 324-1090		9. API NUMBER: 4301530445
6. FIELD AND POOL, OR WILDCAT: BUZZARD BENCH ABO		

COUNTY: EMERY

STATE: UTAH

QTR/GR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 26 18S 07E

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>SURFACE</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<u>COMMINGLE</u>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. proposes to surface commingle the following two wells into our Orangeville CDP:

Federal A 18-7-26 #12; Sec 26-T18S-R07E; 1815' FNL & 897' FWL; 43-015-30445; UTU-67532; Buzzard Bench
Federal T 18-7-22 #34; Sec 22-T18S-R07E; 539' FSL & 1831' FEL; 43-015-30452; UTU-68535; Buzzard Bench

Both of these wells have their own wellhead allocation meter. Both wells will have the sales point or custody transfer at the Orangeville System.

COPY SENT TO OPERATOR

Date: 7-11-05

Initials: CHD

NAME (PLEASE PRINT) HOLLY C. PERKINS TITLE REGULATORY COMPLIANCE TECH
SIGNATURE Holly C. Perkins DATE 6/23/2005

(This space for State use only)

Accepted by the
Utah Division of
Oil, Gas and Mining

Federal Approval Of This
Action Is Necessary

RECEIVED
JUN 29 2005

(5/2000)

Date: 7/18/05 (See Instructions on Reverse Side)

By: Dustin Ducret

Dustin
Ducret ??

DIV. OF OIL, GAS & MINING

IN WELLS FROM COASTAL STATEMENT

	0	302425			
	38990				
	104	104			
	256029				
s Check #	0				
s Check #2	0			0	
	7383			7383	3
	1931		1930 5		
	0				
	304437	302529	1930 5	7383	0

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: XTO ENERGY INC. Operator Account Number: N 2615
Address: 382 CR 3100
city AZTEC
state NM zip 87410 Phone Number: (505) 333-3100

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
4301530679	STATE OF UTAH 17-8-21-33		NWSE	21	17S	8E	EMERY
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
<u>PC</u>	<u>15468</u>	<u>13161</u>	<u>6/15/2006</u>			<u>10/31/07</u>	
Comments: <u>PER 12TH REVISION TO PA "BC" HUNTINGTON (SHALLOW) CBM UNIT</u> <u>FRSD</u>							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

HOLLY C. PERKINS

Name (Please Print)

Signature

Regulatory Compliance Tech 10/24/2007

Title

RECEIVED

OCT 29 2007

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.


1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER:
2. NAME OF OPERATOR: XTO ENERGY INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 382 CR 3100 CITY AZTEC STATE NM ZIP 87410		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: MULTIPLE		8. WELL NAME and NUMBER: MUT ST OF UT 17-8-21-33
5. PHONE NUMBER: (505) 333-3100		9. API NUMBER: MULTIPLE 43 015 30679
6. COUNTY: EMERY		10. FIELD AND POOL, OR WILDCAT:
7. STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: SURFACE
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	COMMINGLE

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. applied for surface commingle on the attached list of wells on 7/5/07 and State of UT DOGM approval was received on 7/13/07. Due to the rejection of the Federal application, XTO would like to withdraw the commingling application and subsequent work will not be done.

NAME (PLEASE PRINT) LORRI D. BINGHAM	TITLE REGULATORY COMPLIANCE TECH
SIGNATURE 	DATE 9/23/2008

(This space for State use only)

RECEIVED
SEP 29 2008

Utah Wells Surface Commingled at Huntington CDP			
Well Name	API #	Status	Lease
American West Group 15-128	43-015-30484	Shut In	State
Conover 14-171	43-015-30529	Producing	State
Gardner Trust 16-121	43-015-30478	Producing	State
Lemmon LM 10-01	43-015-30242	Producing	Federal
Malone 14-131	43-015-30556	Producing	State
Rowley 08-111	43-015-30486	Producing	State
Seeley 08-112	43-015-30495	Producing	State
Seeley Farms 09-117	43-015-30501	Producing	State
State of Utah 16-8-31-12D	43-015-30608	Producing	State
State of Utah 16-8-31-32DX	43-015-30634	Producing	State
State of Utah 16-8-31-44D	43-015-30606	Producing	State
State of Utah 16-8-32-43	43-015-30566	Producing	State
State of Utah 17-8-15-14	43-015-30622	Producing	State
State of Utah 17-8-15-33	43-015-30561	Producing	State
State of Utah 17-8-17-32	43-015-30672	Producing	State
State of Utah 17-8-18-12	43-015-30626	Producing	State
State of Utah 17-8-18-24	43-015-30678	Producing	State
State of Utah 17-8-18-31	43-015-30671	Producing	State
State of Utah 17-8-18-43	43-015-30670	Producing	State
State of Utah 17-8-20-22	43-015-30623	Producing	State
State of Utah 17-8-21-33	43-015-30679	Producing	State
State of Utah 17-8-21-41	43-015-30631	Producing	State
State of Utah 17-8-22-14	43-015-30676	Producing	State
State of Utah 17-8-22-21	43-015-30624	Producing	State
State of Utah 17-8-28-12X	43-015-30699	Producing	State
State of Utah 17-8-3-11X	43-015-30635	Producing	State
State of Utah 17-8-4-21	43-015-30620	Producing	State
State of Utah 17-8-5-42R	43-015-30686	Producing	State
State of Utah 17-8-7-34	43-015-30621	Producing	State
State of Utah 17-8-8-14	43-015-30673	Producing	State
State of Utah 36-138	43-015-30550	Producing	State
State of Utah 36-139	43-015-30530	Producing	State
State of Utah AA 07-105	43-015-30497	Producing	State
State of Utah AA 07-106	43-015-30396	Producing	State
State of Utah AA 07-146	43-015-30569	Producing	State
State of Utah BB 04-116	43-015-30503	Producing	State
State of Utah BB 05-107	43-015-30479	Producing	State
State of Utah BB 05-108	43-015-30480	Producing	State
State of Utah BB 05-109	43-015-30481	P&A	State
State of Utah BB 05-110	43-015-30482	Producing	State
State of Utah BB 08-115	43-015-30496	Shut In	State
State of Utah BB 09-119	43-015-30437	Producing	State
State of Utah BB 09-120	43-015-30444	Producing	State
State of Utah CC 03-161	43-015-30552	Producing	State
State of Utah CC 10-123	43-015-30454	Producing	State
State of Utah CC 10-124	43-015-30438	Producing	State
State of Utah FF 10-125	43-015-30458	Producing	State
State of Utah FF 11-129	43-015-30459	Producing	State
State of Utah FF 11-130	43-015-30462	Shut In	State

should be
on Orangeville
CDP

RECEIVED

SEP 29 2003

DIV. OF OIL, GAS & MINING

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-48176
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: XTO ENERGY INC		7. UNIT or CA AGREEMENT NAME: HUNTINGTON CBM
3. ADDRESS OF OPERATOR: 382 Road 3100 , Aztec, NM, 87410		8. WELL NAME and NUMBER: ST OF UT 17-8-21-33
PHONE NUMBER: 505 333-3159 Ext		9. API NUMBER: 43015306790000
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2433 FSL 1517 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWSE Section: 21 Township: 17.0S Range: 08.0E Meridian: S		9. FIELD and POOL or WILDCAT: BUZZARD BENCH
		COUNTY: EMERY
		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 7/22/2010	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> OTHER: CHEM/NUTRIENT TRT	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. XTO Energy Inc. has injected a chemical/nutrient downhole on this well per the following: 7/22/2010: Shut PU dwn @ 8:30 a.m.. Luca Technology's Injected 2510 BBL's of prod wtr w/ 75 gals of amendment. SWI for 30 days 11:00 p.m.. SICP 0 PSIG, SITP 0 PSIG. Suspend reports for chemical treatment until further activity.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY August 25, 2010		
NAME (PLEASE PRINT) Barbara Nicol	PHONE NUMBER 505 333-3642	TITLE Regulatory Compliance Tech
SIGNATURE N/A	DATE 8/24/2010	